




C.O.G.C.C. Notification Forms

Due to large number of email notices and varying styles of formats COGCC staff has chosen a form that has been used by some EnCana personnel to be the preferred notification form. This should help Operators to provide all the needed information and help COGCC staff to review notices more clearly.

To enter your info type all the info on the GENERAL INFORMATION sheet and it populates to the other sheets.

Notification Form

Operator:	OXY USA WTP LP
Well Name:	CC 697-09-48A
Legal Description:	39.535033-108.222161
COGCC #	66571
API#	050451813400
	WHITE MOUNTAIN RIG
Rig Name and Number:	272
Supervisor:	CODY LONG
Phone number at rig:	1-281-840-6584



Then got the appropriate notice sheet and enter dates and any additional information.

This notice, sent on:

12/31/2010

This is to inform you that we have cemented the 9.625 surface casing on the above mentioned well.

Additionally: Cementing Details

435 BBLS., 12.3#, 2.33 YIELD, 12.62 GAL/SK LEAD CEMENT
(1050 SKS.) 50% EXCESS, 5 BBLS. MINUTE.
59 BBLS. 12.8#, 2.07 YIELD, 10.67 GAL/SK. TAIL CEMENT
(160 SKS) 50 EXCESS, 5 BBLS. MINUTE
DROP PLUG AND DISPLACE WITH 198.3 BBLS. H2O
5 BBLS MIN., LAST 10 BBLS. AT 2 BBLS. MINUTE.
FINAL LIFT PSI. AT 280 PSI. LANDED PLUG AT 780 PSI.
AND HELD 10 MIN., FLOATS HELD.
NO CEMENT RETURNS TO SURFACE
WILL BE DOING TOP JOBS
PUMPED 10.5 BBLS. SUGAR WATER DOWN PARASITE
STRING-NO PRESSURE SPIKES.
TESTED CASING AT 1500 PSI. 30 MINUTES. GOOD TEST

CODY LONG, DSM