

Map Unit Description

Las Animas County Area, Colorado, Parts of Huerfano and Las Animas Counties

SR Saruche-Rombo-Rock outcrop complex, 25 to 50 percent slopes

Setting

Landscape: Foothills
Elevation: 7000 to 8500 feet
Mean annual precipitation: 16 to 22 inches
Mean annual air temperature: 42 to 46 degrees F
Frost-free period: 70 to 100 days

Composition

Saruche and similar soils: 40 percent
Rombo and similar soils: 35 percent
Rock outcrop: 15 percent

Description of Saruche

Setting

Landform: Hills
Landform position (two-dimensional): Backslope, shoulder
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Slope alluvium and residuum weathered from shale

Properties and Qualities

Slope: 25 to 50 percent
Surface area covered with stones and boulders: 30.0 percent
Depth to restrictive feature: 20 to 40 inches to Paralithic bedrock; 8 to 20 inches to Paralithic bedrock
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately low or moderately high (0.06 to 0.20 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 0 percent
Gypsum maximum: 0 percent
Available water capacity: Very low (about 2.6 inches)

Interpretive Groups

Land capability (non irrigated): 7e
Ecological site: Shrubby Foothill (R049XF223CO)

Typical Profile

0 to 4 inches: channery silty clay loam
4 to 16 inches: parachannery silty clay loam
16 to 20 inches: bedrock
20 to 30 inches: bedrock

Description of Rombo

Setting

Landform: Hills
Landform position (two-dimensional): Backslope, footslope
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Slope alluvium and residuum weathered from shale and siltstone

Properties and Qualities

Slope: 25 to 50 percent
Surface area covered with stones and boulders: 30.0 percent
Depth to restrictive feature: 20 to 40 inches to Paralithic bedrock
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Very low or moderately low (0.00 to 0.06 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 5 percent
Gypsum maximum: 0 percent
Sodium adsorption ratio maximum: 2.0
Available water capacity: Low (about 5.4 inches)

Map Unit Description

Las Animas County Area, Colorado, Parts of Huerfano and Las Animas Counties

Interpretive Groups

Land capability (non irrigated): 7e

Ecological site: Shrubby Foothill (R049XF223CO)

Typical Profile

0 to 4 inches: channery silty clay loam

4 to 22 inches: channery silty clay loam

22 to 34 inches: parachannery silty clay loam

34 to 44 inches: bedrock

Description of Rock outcrop

Setting

Landform: Scarps

Parent material: Sandstone

Properties and Qualities

Slope: 35 to 50 percent

Depth to restrictive feature: 0 to 0 inches to Lithic bedrock

Capacity of the most limiting layer to transmit water (Ksat): Very low or moderately high (0.00 to 0.20 in/hr)

Interpretive Groups

Land capability (non irrigated): 8s

Typical Profile

0 to 60 inches: bedrock