

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refilling ☐
Sidetrack ☐

Document Number:

400115047

Plugging Bond Surety

20100017

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Heather Mitchell Phone: (720)876-3070 Fax: (720)876-4070
Email: heather.mitchell@encana.com

7. Well Name: N. Parachute Well Number: EF08A-34 P27595

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 11409

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 27 Twp: 5S Rng: 95W Meridian: 6

Latitude: 39.579225 Longitude: -108.033122

Footage at Surface: 601 feet FNL/FSL FSL 535 feet FEL/FWL FEL

11. Field Name: Grand Valley Field Number: 31290

12. Ground Elevation: 6650 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 11/01/2008 PDOP Reading: 2.1 Instrument Operator's Name: Robert Kay

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FNL/FWL
1323 FNL 659 FEL 1323 FNL 659 FEL
Sec: 34 Twp: 5S Rng: 95W Sec: 34 Twp: 5S Rng: 95W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 19500 ft

18. Distance to nearest property line: 535 ft 19. Distance to nearest well permitted/completed in the same formation: 206 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	510-49		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Please see attached maps

25. Distance to Nearest Mineral Lease Line: 659 ft 26. Total Acres in Lease: 25889

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Recycle and bury

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Line Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	Linepipe		120	117	120	0
SURF	12+1/4	9+5/8	36#		1,800	383	1,800	0
2ND	8+3/4	4+1/2	11.6#		11,409	592	11,409	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Encana owns surface and minerals. # 17 is calculated from the nearest utility. Conductor and surface casing will be run to surface. The size of the production hole is both 8-3/4" and 7-7/8". Production casing is set 200' above the WMFK.

34. Location ID: 335806

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Heather Mitchell

Title: Regulatory Analyst Date: 12/13/2010 Email: heather.mitchell@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 1/9/2011

API NUMBER

05 045 20288 00

Permit Number: _____ Expiration Date: 1/8/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1)COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2)GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

Attachment Check List

Att Doc Num	Name
400115047	FORM 2 SUBMITTED
400116006	PLAT
400116007	DEVIATED DRILLING PLAN
400116008	OTHER
400116009	LEASE MAP
400116010	TOPO MAP

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)