

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refilling ☐  
Sidetrack ☐

Document Number:

400117102

Plugging Bond Surety

20040105

3. Name of Operator: BERRY PETROLEUM COMPANY

4. COGCC Operator Number: 10091

5. Address: 1999 BROADWAY STE 3700

City: DENVER State: CO Zip: 80202

6. Contact Name: Kallasandra Moran Phone: (303)999-4225 Fax: (303)999-4325  
Email: kmoran@bry-consultant.com

7. Well Name: School House Point Well Number: OM 07D B21 696

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 9811

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 21 Twp: 6S Rng: 96W Meridian: 6

Latitude: 39.513587 Longitude: -108.108855

Footage at Surface: 790 feet FNL/FSL 1182 feet FEL/FWL FEL

11. Field Name: Grand Valley Field Number: 31290

12. Ground Elevation: 8286 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 11/10/2010 PDOP Reading: 2.1 Instrument Operator's Name: Robert Wood / Construction Surveys Inc

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2305 FNL 1879 FEL 2305 FNL 1879 FEL 2305  
Sec: 21 Twp: 6S Rng: 96W Sec: 21 Twp: 6S Rng: 96W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 2306 ft

18. Distance to nearest property line: 2369 ft 19. Distance to nearest well permitted/completed in the same formation: 461 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	510-13		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
See attached mineral lease map.

25. Distance to Nearest Mineral Lease Line: 842 ft 26. Total Acres in Lease: 25000

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☒ Yes ☐ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Total closed loop system

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Line Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	30	20	55	0	90	100	90	0
SURF	16	9+5/8	36	0	2,500	1,000	2,500	0
1ST	7+7/8	4+1/2	11.6		9,811	600	9,811	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments The pad has not been built. Pit has not been constructed. The proposed well has not been drilled. The conductor has not been set. No rig on site. The location does not require a variance from any of the rules listed in Rule 306.d. (1). (A). (ii). The location is not in a restricted surface occupancy area. The location is in a sensitive wildlife habitat area for Elk production. The production casing Top of Cement will be 200' above the Top of Gas

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Kallasandra M. Moran

Title: Permit Agent Date: 12/15/2010 Email: kmoran@bry-consultant.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 1/9/2011

API NUMBER

05 045 20302 00

Permit Number: \_\_\_\_\_ Expiration Date: 1/8/2013

CONDITIONS OF APPROVAL, IF ANY: \_\_\_\_\_

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3) THE NEARBY HILLSIDE MUST BE MONITORED FOR ANY DAY LIGHTING DRILLING FLUIDS THROUGHOUT THE DRILLING OF THE SURFACE CASING INTERVAL.

4) COMPLY WITH ALL PROVISIONS OF THE JUNE 12, 2008 NOTICE TO OPERATORS DRILLING WELLS WITHIN 3/4 MILE OF THE RIM OF THE ROAN PLATEAU IN GARFIELD COUNTY - PIT DESIGN, CONSTRUCTION AND MONITORING REQUIREMENTS. SEE ATTACHED NOTICE.

5) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name
400117102	FORM 2 SUBMITTED
400117103	PLAT
400117104	DEVIATED DRILLING PLAN
400117105	OTHER
400117106	MINERAL LEASE MAP
400117107	TOPO MAP
400117108	30 DAY NOTICE LETTER

Total Attach: 7 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Changed Line 17 - Distance to nearest building, public road, above ground utility or railroad from 15103' RR to 2306' utility per the hydrology map and Line 18 - Distance to property line from 842' from bottom hole to 2369' from surface per the well plat.	12/27/2010 12:36:07 PM

Total: 1 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>

Total: 0 comment(s)