



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198723

Date 12/9/2010	Well Owner KERR/McGEE	Well No. 15-33	Lease COTTON WOOD
County WELD	State COLORADO	Field	
Charge to KERR/McGEE OIL & GAS ONSHORE, LP	Charge Code		For Office Use Only
Address 1999 BROADWAY STE 3700 (PATTERSON #189)			
City, State DENVER, COLORADO 80202			
Pump Truck No. 1201	Code	Bulk Truck No. 1219/1214	Code
Type of Job	Depth	Fl. 995	To
Surface 8 3/4" CSG-24"	Bottom of Surface	Fl. 986	To
Plug	Plug Landed @ 942	Fl. Time On 0200	
Production	Pipe Landed @ 986	Fl. Plug Down 0540	

Reference No.	Description	Qty.	Meas.	Unit Price	Amount		
	Pump Truck Charge						
	Cement Neat TYPE III	620	SKS				
	Poz. Mix		MIKE LINGREEN				
	Calcium Chloride	2.570					
	Gel % Flo-Cele 1/4" Per Sack		User ID ZMDL6				
	Handling Charge		WBSA W/ICE	2040330.0RL			
	Hauling Charge		G/L Acct.	80012090			
	Additional Cement						
	MIXING RATE 4 BPM		PRE-FLUSH	0452-0458			
	DISP RATE 5 BPM		MIX	0458-0525			
	SLURRY VOL 1.32 CU FT/SK		CHANGE VALVE	0525-0528			
	SLURRY WT 14.8-15.0 PPG		DISPLACE	0528-0540			
	WATER/CEMENT 6.25 GAL/SK		FINAL LIFT	480			
	TOTAL SLURRY VOL 145.5 BBLs CEMENT						
	PLUG LANDED @ 500 PSI						
	WATER TEMP 67						
Books:	PRE FLUSH W/ 30 BBLs H²O	Tax Reference Code		Sub Total			
	DISPLACE W/ 60 BBLs H²O	State CO 2.9 %		Tax			
	CIRCULATE 4 BBLs CEMENT	Disc.		Total			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		60			
1214/1218		Bulk Truck		60/60			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JIM/SAM/OSCAR/TRADES**

Received By **Shay Harrison**
Customer or His Agent