

## Kubeczko, Dave

---

**From:** Kubeczko, Dave  
**Sent:** Tuesday, January 11, 2011 11:09 AM  
**To:** Kubeczko, Dave  
**Subject:** FW: Sunterra; Booco's Contract Services Inc., Robert Waltrip No. 1H-3, SWSW Sec 3 T6N R87W, Routt County, Form 2A (#400101720) Review

Scan No 2033583      CORRESPONDENCE      2A#400101720

---

**From:** Jordan Wells [mailto:jordan.d.wells@gmail.com]  
**Sent:** Monday, January 10, 2011 10:55 AM  
**To:** Kubeczko, Dave  
**Subject:** Re: Sunterra; Booco's Contract Services Inc., Robert Waltrip No. 1H-3, SWSW Sec 3 T6N R87W, Routt County, Form 2A (#400101720) Review

Dave,  
Thanks for your information, we agree and will comply.  
Thanks,  
Jordan d wells

On Jan 7, 2011 12:44 PM, "Kubeczko, Dave" <[Dave.Kubeczko@state.co.us](mailto:Dave.Kubeczko@state.co.us)> wrote:

Jordan,

I have been reviewing the Robert Waltrip No. 1H-3 **Form 2A** (#400101720). I sent an email (attached below) to Randy Booco on 12-21-2010 requesting clarifications regarding the data Booco's Contract Services has submitted on or attached to the Form 2A; as well as requesting concurrence with attaching some COAs. I am forwarding this email to you for your review. COGCC would appreciate your concurrence with attaching the COAs (items 1 and 2 below) to the Form 2A permit prior to passing the OGLA review. The other issue (item 1 below) also needs to be addressed prior to permit approval. If you have any questions, please do not hesitate to call me at (970) 309-2514 (cell), or email. Thanks.

Dave

**David A. Kubeczko, PG**

**Oil and Gas Location Assessment Specialist**

Colorado Oil & Gas Conservation Commission

Northwest Area Office  
707 Wapiti Court, Suite 204  
Rifle, CO 81650  
Phone: (970) 625-2497x5  
FAX: (970) 625-5682  
Cell: (970) 309-2514  
[dave.kubeczko@state.co.us](mailto:dave.kubeczko@state.co.us)



---

**From:** Kubeczko, Dave  
**Sent:** Tuesday, December 21, 2010 8:55 AM  
**To:** [boocosinc@aol.com](mailto:boocosinc@aol.com)  
**Subject:** Booco's Contract services Inc., Robert Waltrip No. 1H-3, SWSW Sec 3 T6N R87W, Routt County, Form 2A (#400101720) Review

Randy,

I have been reviewing the Robert Waltrip No. 1H-3 **Form 2A** (#400101720). COGCC requests the following clarifications regarding the data Booco's Contract Services has submitted on or attached to the Form 2A. In addition, COGCC would like to attach the following conditions of approval (COAs) to the Form 2A prior to passing the Oil and Gas Location Assessment (OGLA) review.

1. **Water Resources (Section 14):** Form 2A indicates that the distance to the nearest surface water is 3150 feet. COGCC's rules state that the distance to the nearest surface water should reflect intermittent (this includes ephemeral streams, irrigation ditches, drainages), as well as,

perennial streams. COGCC review indicates a closer stream (possibly intermittent) located approximately 898 feet to the west-northwest. I can make this change if you send an email with this request. The following conditions of approval (COAs) will apply:

**COA 4** - Operator must ensure 110 percent secondary containment for any volume of fluids contained at well site during drilling and completion operations.

**COA 5** - Operator must implement best management practices to contain any unintentional release of fluids, including any fluids conveyed via temporary surface pipelines.

2. **General:** The following conditions of approval (COAs) will apply:

**COA 6** - Reserve pit (if constructed, as shown on the construction layout drawings) must be lined or a closed loop system (which Booco has indicated on the Form 2A) must be implemented during drilling. Any other pit constructed (frac pit) must be lined.

**COA 38** - The moisture content of any drill cuttings in a cuttings pit, trench, or pile shall be as low as practicable to prevent accumulation of liquids greater than de minimis amounts. At the time of closure, the drill cuttings must also meet the applicable standards of table 910-1.

COGCC would appreciate your concurrence with attaching these COAs (items 1 and 2) to the Form 2A permit prior to passing the OGLA review. The other issue (item 1) also needs to be addressed prior to permit approval. If you have any questions, please do not hesitate to call me at (970) 309-2514 (cell), or email. Thanks.

Dave

**David A. Kubeczko, PG**

**Oil and Gas Location Assessment Specialist**

Colorado Oil & Gas Conservation Commission

Northwest Area Office

707 Wapiti Court, Suite 204

Rifle, CO 81650

Phone: (970) 625-2497x5

FAX: (970) 625-5682

Cell: (970) 309-2514

[dave.kubeczko@state.co.us](mailto:dave.kubeczko@state.co.us)



 *Please consider the environment before printing this e-mail*