



**CEMENTER'S WELL SERVICE, INC.**  
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198601

Date <u>11/2/2010</u>	Well Owner <u>KERR/McGEE</u>	Well No. <u>13-7</u>	Lease <u>MAPLEWOOD</u>
County <u>WELD</u>	State <u>COLORADO</u>	Field	
Charge to <u>KERR/McGEE OIL &amp; GAS ONSHORE, LP</u>	Charge Code		For Office Use Only
Address <u>1999 BROADWAY STE 3700 (XTREME#8)</u>			
City, State <u>DENVER, COLORADO 80202</u>			
Pump Truck No. <u>1201</u>	Code	Bulk Truck No. <u>1214/21</u>	Code
Type of Job	Depth	Ft. <u>830</u>	To
Surface <u>8 5/8" CSG-24"</u>	Bottom of Surface	Ft. <u>819</u>	To
Plug	Plug Landed @ <u>775</u>	Ft. Time On <u>1900</u>	
Production	Pipe Landed @ <u>819</u>	Ft. Time Off <u>PLUG DOWN 2100</u>	

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat <u>TYPE III</u>	<u>520</u>	<u>SKS</u>		
	Poz. Mix				
	Calcium Chloride	<u>2.570</u>	<u>User ID ZMDLG</u>		
	Gel % Flo-Cele <u>1/4 #Per Sack</u>				
	Handling Charge			<u>WBS/NOICC 2069293.DRL</u>	
	Hauling Charge			<u>G/L Acct 800/2090</u>	
	Additional Cement				
	<u>MIXING RATE 4 BPM</u>		<u>PREFLUSH</u>	<u>2020-2024</u>	
	<u>DISP RATE 5 BPM</u>		<u>MIX</u>	<u>2024-2047</u>	
	<u>SLURRY VOL 1.32 CU FT / SK</u>		<u>CHANGE VALVES</u>	<u>2047-2050</u>	
	<u>SLURRY WT 14.8-15.0 PPG</u>		<u>DISPLACE</u>	<u>2050-2100</u>	
	<u>WATER/CEMENT 6.25 GAL/SK</u>		<u>FINAL IFT</u>	<u>370</u>	
	<u>WATER TEMP 57</u>				
	<u>TOTAL SLURRY VOL 122 BBS CEMENT</u>				
	<u>PLUG LANDED @ 580 PSI</u>				
	<u>PRE-FLUSH w/20 BBS H2O</u>				
	<u>DISPLACE w/49 BBS H2O</u>				
	<u>CIRCULATE 7 BBS CEMENT</u>				
	Tax Reference Code			Sub Total	
	State <u>00219</u> %			Tax	
	Disc.			Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1201</u>		Pump Truck		<u>50</u>			
<u>1214/21</u>		Bulk Truck		<u>50/50</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM/SAM TRAVIS

Received By Craig Jones

Customer or His Agent