



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 198538

Date <u>11/6/2010</u>	Well Owner <u>KERR/McGEE</u>	Well No. <u>22-7</u>	Lease <u>MAPLEWOOD</u>
County <u>WELD</u>	State <u>COLORADO</u>	Field	
Charge to <u>KERR/McGEE OIL &amp; GAS ONSHORE, LP</u>	Charge Code		
Address <u>1999 BROADWAY STE 3700 (XTREME #8)</u>	For Office Use Only		
City, State <u>DENVER, COLORADO 80202</u>			
Pump Truck No. <u>1201</u>	Code	Bulk Truck No. <u>218/214</u>	Code
Type of Job	Depth	Pl. <u>830</u>	To
Surface <u>8 5/8" CSG 24"</u>	Bottom of Surface	Pl. <u>820</u>	To
Plug	Plug Landed @ <u>776</u>	Pl. Time On <u>0100</u>	
Production	Pipe Landed @ <u>820</u>	Pl. Time Off <u>0320</u>	

Reference No.	Description	Qty.	Meas.	Unit Price	Amount		
	Pump Truck Charge						
	Cement Neat TYPE III	520	SKS				
	Poz. Mix						
	Calcium Chloride	2.5%	User ID ZMDL6				
	Gel % Flo-Cele 1/4 #Per Sack						
	Handling Charge			WBS/MO/CC 2039280 DRL			
	Hauling Charge			G/L Acct. 80012090			
	Additional Cement						
	MIXING RATE 4 BPM		PRE FLUSH	0238-0244			
	DISP RATE 5BPM		MIX	0244-0307			
	SLURRY VOL 1.32 CU FT <sup>3</sup> /SK		CHANGE VALVES	0307-0310			
	SLURRY WT 14.8-15.0 PPG		DISPLACE	0310-0320			
	WATER/CEMENT 6.25 GAL/SK		FINAL LIFT	367			
	TOTAL SLURRY VOL 122 BBLS CEMENT						
	PLUG LANDED @ 375 PSI						
	WATER TEMP 49						
	PRE FLUSH w/ 30 BBLS H <sub>2</sub> O		Tax Reference Code	Sub Total			
	DISPLACE w/ 49 BBLS H <sub>2</sub> O		State CO 2.9 %	Tax			
	CIRCULATE 5 BBLS CEMENT		Disc.	Total			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		82			
214/218		Bulk Truck		82/82			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM/SAM/OSCAR TRAILIS

Received By Craig Jones  
Customer or His Agent