

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400096977

Plugging Bond Surety

20070004

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY LLC

4. COGCC Operator Number: 8960

5. Address: P O BOX 21974

City: BAKERSFIELD State: CA Zip: 93390

6. Contact Name: Keith Caplan ext 203 Phone: (720)279-2330 Fax: (720)279-2331

Email: KCaplan@bonanzacrk.com

7. Well Name: Antelope Well Number: 22-31

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 6850

WELL LOCATION INFORMATION

10. QtrQtr: SENW Sec: 31 Twp: 5N Rng: 62W Meridian: 6

Latitude: 40.359470 Longitude: -104.370590

Footage at Surface: 1400 feet FNL/FSL 1322 feet FEL/FWL
FNL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4588 13. County: WELD

14. GPS Data:

Date of Measurement: 09/16/2010 PDOP Reading: 2.3 Instrument Operator's Name: Dan Griggs

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL FWL Bottom Hole: FNL/FSL FNL FWL
1980 FNL 1980 FWL 1980 FNL 1980 FWL
Sec: 31 Twp: 5N Rng: 62W Sec: 31 Twp: 5N Rng: 62W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 5280 ft

18. Distance to nearest property line: 1322 ft 19. Distance to nearest well permitted/completed in the same formation: 5280 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara-Codell	NB-CD		40	SENW

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20070001

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T4N, R62W: Sec. 3: Lot 2, S/2 NW/4; Sec. 5: Lots 1 & 2, S/2 N/2, S/2; Sec. 17: N/2 N/2, S/2 NE/4; Sec. 18: N/2 of Lot 1, NE/4 NW/4, N/2 NE/4, (N/2 N/2); T4N, R63W: Sec. 1: Lots 1 & 2, S/2 N/2, S/2; Sec. 2: Lots 1 & 2, S/2 N/2, NE/4 SW/4, SE/4; Sec. 12: All; T5N, R62W: Sec. 3: Lot 2, SW/4 NE/4, W/2 SE/4; Sec. 15: W/2 E/2, W/2; Sec. 17: All; Sec. 18: SE/4; Sec. 19: Lots 3 & 4, E/2 SW/4, E/2; Sec. 20: W/2; Sec. 21: All; Sec. 29: All; Sec. 31: Lots 1, 2, 3, 4, E/2 W/2, E/2 (All); Sec. 33: N/2; T5N, R63W: Sec. 34: SE/4 NE/4, SE/4; Sec. 35: S/2; Sec. 36: SW/4 SW/4.

25. Distance to Nearest Mineral Lease Line: 1980 ft 26. Total Acres in Lease: 8115

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24		400	260	400	0
1ST	7+7/8	4+1/2	11.6		6,850	247	6,850	5,800

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used on this well.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Keith Caplan

Title: Sr. Operations Technician Date: 12/22/2010 Email: KCaplan@bonanzacrk.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 1/20/2011

API NUMBER

05 123 32843 00

Permit Number: _____ Expiration Date: 1/19/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hr notice of spud to Bo Brown at 970-330-6085 or email at bo.brown@state.co.us .
- 2) Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC.
- 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
2565805	SURFACE CASING CHECK
400096977	FORM 2 SUBMITTED
400111124	PLAT
400118829	DEVIATED DRILLING PLAN

Total Attach: 4 Files

General Comments

User Group	Comment	Comment Date
Permit	Changed to bonding on only to protect surface owners that do not have mineral interest. SUA in the works.	12/28/2010 8:48:29 AM
Permit	Surface owner is the mineral owner but bonding on is checked.	12/27/2010 12:42:46 PM

Total: 2 comment(s)

BMP

Type	Comment

Total: 0 comment(s)