

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400112681

Plugging Bond Surety

20030058

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: EOG RESOURCES INC

4. COGCC Operator Number: 27742

5. Address: 600 17TH ST STE 1100N

City: DENVER State: CO Zip: 80202

6. Contact Name: Nanette Lupcho Phone: (435)781-9157 Fax: (435)789-7633

Email: nanette\_lupcho@eogresources.com

7. Well Name: Critter Creek Well Number: 14-18H

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 12529

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 18 Twp: 11N Rng: 63W Meridian: 6

Latitude: 40.916439 Longitude: -104.468217

Footage at Surface: 501 feet FNL/FSL FSL 501 feet FEL/FWL FEL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 5348 13. County: WELD

14. GPS Data:

Date of Measurement: 04/08/2010 PDOP Reading: 1.0 Instrument Operator's Name: Robert Kay

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 695 FSL 938 FEL 1850 FNL 600 FEL/FWL FWL  
Sec: 18 Twp: 11N Rng: 63W Sec: 18 Twp: 11N Rng: 63W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 495 ft

18. Distance to nearest property line: 501 ft 19. Distance to nearest well permitted/completed in the same formation: 1380 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	421-3	640	ALL

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
Please see attached sheet

25. Distance to Nearest Mineral Lease Line: 600 ft 26. Total Acres in Lease: 1001

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Backfill and Cover

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16						
1ST	13+1/2	9+5/8	36		1,450	755	1,450	0
2ND	8+3/4	7	23		7,788	825	7,788	0
1ST LINER	6	4+1/2	11.6		12,529	340	12,529	7,038

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments \_\_\_\_\_

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Nanette Lupcho

Title: Regulatory Assistant Date: 12/1/2010 Email: nanette\_lupcho@eogresources.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 1/21/2011

<b>API NUMBER</b> 05 123 32868 00	Permit Number: _____ Expiration Date: <u>1/20/2013</u>
--------------------------------------	--

**CONDITIONS OF APPROVAL, IF ANY:** \_\_\_\_\_

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hr notice of MIRU to Bo Brown at 970-330-6085 or email at bo.brown@state.co.us.
- 2) Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC.
- 3) If completed, provide cement coverage from the intermediate casing shoe to a minimum of 200' above Niobrara. Verify cement with a cement bond log.
- 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Attachment Check List**

Att Doc Num	Name
2566289	SURFACE CASING CHECK
400112681	FORM 2 SUBMITTED
400112725	DRILLING PLAN
400112727	DEVIATED DRILLING PLAN
400112728	TOPO MAP
400112770	PLAT
400112774	LEGAL/LEASE DESCRIPTION

Total Attach: 7 Files

### **General Comments**

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### **BMP**

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)