

FORM
5A

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400122851

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120 4. Contact Name: Kenny Trueax
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6383
3. Address: P O BOX 173779 Fax: (720) 929-7383
City: DENVER State: CO Zip: 80217-37

5. API Number 05-123-24335-00 6. County: WELD
7. Well Name: REYNOLDS Well Number: 27-24
8. Location: QtrQtr: NENE Section: 24 Township: 3N Range: 68W Meridian: 6
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: <u>CODELL</u>	Status: <u>COMMINGLED</u>
Treatment Date: <u>12/01/2006</u>	Date of First Production this formation: <u>12/06/2006</u>
Perforations Top: <u>7328</u> Bottom: <u>7348</u>	No. Holes: <u>60</u> Hole size: <u>0.45</u>
Provide a brief summary of the formation treatment:	Open Hole: <input type="checkbox"/>
<u>Commingled with Niobrara</u>	
This formation is commingled with another formation: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
Test Information:	
Date: _____ Hours: _____	Bbls oil: _____ Mcf Gas: _____ Bbls H2O: _____
Calculated 24 hour rate: _____	Bbls oil: _____ Mcf Gas: _____ Bbls H2O: _____ GOR: _____
Test Method: _____	Casing PSI: _____ Tubing PSI: _____ Choke Size: _____
Gas Disposition: _____	Gas Type: _____ BTU Gas: _____ API Gravity Oil: _____
Tubing Size: _____	Tubing Setting Depth: _____ Tbg setting date: _____ Packer Depth: _____
Reason for Non-Production: _____	
Date formation Abandoned: _____ Squeeze: <input type="checkbox"/> Yes <input type="checkbox"/> No If yes, number of sacks cmt _____	
Bridge Plug Depth: _____ Sacks cement on top: _____	

FORMATION: NIOBRARA-CODELL Status: PRODUCING

Treatment Date: 12/01/2010 Date of First Production this formation: 12/16/2010

Perforations Top: 7064 Bottom: 7200 No. Holes: 124 Hole size: 0.42

Provide a brief summary of the formation treatment: Open Hole: ☐

NB Perf: 7064-7200 Holes: 64 Size: .42
Frac NB w/ 250 gal 15% HCl & 239,256 gal Slickwater w/ 200,640# 40/70 sand, 4,000# SB Excel sand
CD Perf: 7328-7348 Holes: 60 Size: .45 (no new perf)
Frac CD w/ 165,849 gal Slickwater w/ 115,640# 40/70 sand, 4,000# SB Excel sand

This formation is commingled with another formation: ☐ Yes ☒ No

Test Information:

Date: 01/09/2011 Hours: 24 Bbls oil: 33 Mcf Gas: 186 Bbls H2O: 0

Calculated 24 hour rate: Bbls oil: 33 Mcf Gas: 186 Bbls H2O: 0 GOR: 5636

Test Method: Flowing Casing PSI: 949 Tubing PSI: 310 Choke Size: 16/64

Gas Disposition: SOLD Gas Type: WET BTU Gas: 1205 API Gravity Oil: 47

Tubing Size: 2 + 3/8 Tubing Setting Depth: 7306 Tbg setting date: 12/13/2010 Packer Depth: _____

Reason for Non-Production:

Date formation Abandoned: _____ Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt _____

Bridge Plug Depth: _____ Sacks cement on top: _____

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kenny Trueax

Title: Regulatory Analyst II Date: 1/13/2011 Email Kenny.Trueax@anadarko.com

Based on the information provided herein, this Completed Interval Report (Form 5A) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 1/21/2011

Attachment Check List

Att Doc Num	Name
400122851	FORM 5A SUBMITTED

Total Attach: 1 Files

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)