



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198841

Date <u>1/10/2011</u>	Well Owner <u>KERR MCGEE</u>	Well No. <u>33-33</u>	Lease <u>COTTONWOOD</u>
County <u>WELD</u>	State <u>COLORADO</u>	Field	
Charge to <u>KERR MCGEE OIL & GAS ONSHORE, LP</u>	Charge Code		For Office Use Only
Address <u>1999 BROADWAY, SUITE 3700 (PATTERSON #189)</u>			
City, State <u>DENVER, COLORADO 80202</u>			
Pump Truck No. <u>1201</u>	Code	Bulk Truck No. <u>214/217</u>	Code
Type of Job	Depth	Fl. <u>1003</u>	To
Surface <u>8" CSO-24"</u>	Bottom of Surface	Fl. <u>992</u>	To
Plug	Plug Landed @ <u>948</u>	Time On <u>1700</u>	
Production	Pipe Landed @ <u>992</u>	Time Off <u>PLUG DOWN 2100</u>	

Reference No.	Description	Qty.	Meas.	Unit Price	Amount		
	Pump Truck Charge						
	Cement Nod ✓ TYPE III	630	SKS				
	Poz. Mix						
	Calcium Chloride	25%	MIKE LINSREEN				
	Gel % Flo-Cole 1/4#Per Sack		User ID ZMDL6				
	Handling Charge		NBSAWOCC	2040332.DRL			
	Hauling Charge		G/L Acct.	80012090			
	Additional Cement						
	MIXING RATE-4BPM	PRE-FLUSH	2012-2014				
	DISP RATE-5BPM	MIXING	2018-2045				
	SLURRY VOL-1.33 ³ CU.FT/SK	CHANGE VALVES	2046-2048				
	SLURRY WT 14.8-15.0 PPG	DISP.	2048-2100				
	WATER/CEMENT-6.25 GAL/SK	FINAL TET @	500PSI				
	WATER TEMP. 55						
	TOTAL SLURRY 148 BBLs CEMENT						
	LANDED PLUG @ 520PSI						
Remarks:	PRE-FLUSH W/30 BBLs H ₂ O	Tax Reference Code	Sub Total				
	DISPLACE W/60 BBLs H ₂ O	State CO 2.9%	Tax				
	CIRCULATE 3 BBLs CEMENT	Disc.	Total				
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		64			
124/217		Bulk Truck		64/64			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM, OSCAR, STEVE, ADAM

Received By Aug. Herman
Customer or His Agent