



02054849

FORM 23 Rev 6/99

### State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 (303) 894-2100 Fax: (303) 894-2109



**RECEIVED**  
JAN 17 2011  
**COGCC**

### LOSS OF WELL CONTROL REPORT

As required by Rule 327.

1. OGCC Operator Number: 10071	4. Contact Name & Phone MATT BARBER	Report taken by: <i>DAVE ANDREWS</i>
2. Name of Operator: BILL BARRETT CORP	Ph: 303-312-8186	
3. Address: 1099 18TH STREET, SUITE 2300 City: DENVER State: COLO Zip: 80202	Fax: 303-291-0420	

### WELL LOCATION INFORMATION

5. API Number: 05-045-18662	6. County: GARFIELD
7. Well Name: MILLER FED# 23C-6-791	8. Well Number: 23C-6-791
9. Unit Name (if appl.):	10. Unit No:
11. Qtr: NWSE LOT 2 Sec: 6 Twp: 7S Rng: 91W Meridian: 6TH PM	
12. Footage From Exterior Section Lines: 32 FNL, 2423 FEL	
13. Field Name: MAMM CREEK	14. Field Number: 52500

### CASING INFORMATION

15. Surface Casing Size: 9 5/8" / Weight per Foot: 36 Grade: J 55 True Vertical Setting Depth: 674.00
16. Intermed. Casing Size: / Weight per Foot: Grade: True Vertical Setting Depth:

### KICK INFORMATION

17. True Vertical Depth at Kick: 7011.49	19. Formation Code: RLNS
18. Formation at Kick: ROLLINS	
20. Shut-in Drill Pipe Pressure (SIDPP): 550 psi	
21. Shut-in Casing Pressure (SICP): 650 psi	
22. Mud Weight at Time of Kick: 10.2 ppg	
23. Pit Gain: 80 bbls	
24. Time and Date Shut In: 2:30 AM 1/7/11	
25. Mud Weight Required to Control Well: 10.8 ppg	
26. Type of Kick: <input checked="" type="checkbox"/> Gas <input type="checkbox"/> Oil <input type="checkbox"/> Water	
27. Comments (describe actions to control in detail): HAD TO RAISE PH TO 11. TO KILL WHAT WAS MOSTLY C O/2. WE WERE ON CHOKE FOR APPROX 8 HRS. AND THEN WENT STRICTLY TO GAS BUSTER FOR 4 HRS. AND WELL WAS STATIC.	