

FORM
5A

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400124889

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120 4. Contact Name: CARA MAHLER
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6029
3. Address: P O BOX 173779 Fax: (720) 929-7029
City: DENVER State: CO Zip: 80217-37

5. API Number 05-123-31439-00 6. County: WELD
7. Well Name: MAPLEWOOD Well Number: 13-7
8. Location: QtrQtr: SWSW Section: 7 Township: 4N Range: 67W Meridian: 6
9. Field Name: _____ Field Code: _____

Completed Interval

FORMATION: NIOBARRA-CODELL Status: PRODUCING
Treatment Date: 01/03/2011 Date of First Production this formation: 01/12/2011
Perforations Top: 6823 Bottom: 7132 No. Holes: 120 Hole size: 0.38
Provide a brief summary of the formation treatment: Open Hole: ☐
NB PERF 6823-6996 HOLES 60 SIZE 0.38 CD PERF 7112-7132 HOLES 60 SIZE 0.38
Frac Niobrara A & B & C down 4-1/2" Csg w/ 250 gal 15% HCl & 244,851 gal Slickwater w/ 200,400# 40/70, 4,000# SB Excel.
Frac Codell down 4-1/2" Csg w/ 207,621 gal Slickwater w/ 150,440# 40/70, 4,000# SB Excel.
This formation is commingled with another formation: ☐ Yes ☒ No
Test Information:
Date: 01/17/2011 Hours: 24 Bbls oil: 48 Mcf Gas: 109 Bbls H2O: 0
Calculated 24 hour rate: Bbls oil: 48 Mcf Gas: 109 Bbls H2O: 0 GOR: 2271
Test Method: FLOWING Casing PSI: 1000 Tubing PSI: 800 Choke Size: 18/64
Gas Disposition: SOLD Gas Type: WET BTU Gas: 1501 API Gravity Oil: 48
Tubing Size: _____ Tubing Setting Depth: _____ Tbg setting date: _____ Packer Depth: _____
Reason for Non-Production: _____
Date formation Abandoned: _____ Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt _____
Bridge Plug Depth: _____ Sacks cement on top: _____

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CARA MAHLER

Title: REGULATORY ANALYST 1 Date: 1/19/2011 Email CARA.MAHLER@ANADARKO.COM

Based on the information provided herein, this Completed Interval Report (Form 5A) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 2/1/2011

Attachment Check List

Att Doc Num	Name
400124889	FORM 5A SUBMITTED

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)