



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 198592

Date	11-2-10	Well Owner	KERR MCGEE	Well No.	31-27	Lease	DAY CREEK
County	WELD	State	COLORADO			Field	
Charge to	KERR MCGEE OIL & GAS ONSHORE, LP					Charge Code	
Address	1999 BROADWAY SUITE 3700 (XTREME-12)					For Office Use Only	
City, State	DENVER COLORADO 80202						
Pump Truck No.	002	Code		Bulk Truck No	1217/1216	Code	
Type of Job				Depth	Fl. 1201	To	
Surface	8 5/8" CSG - 24ft			Bottom of Surface	Fl. 1191	To	
Plug				Plug Landed @	1146	Time On	0915
Production				Pipe Landed @	1191	Time Off	PLUG DOWN 1500

Reference No.	Description	Qty.	Meas.	Unit Price	Amount		
	Pump Truck Charge						
	Cement Mix TYPE III	750	SKS				
	Poz. Mix						
	Calcium Chloride	25%	MIKE LINGREEN				
	Gel % Flo-Cele 4 #Per Sack		User ID ZMDLB				
	Handling Charge		WBS/WHO/CC 2036577				
	Hauling Charge		GL Acct 80012090				
	Additional Cement						
MIX RATE 4 BPM	PREFLUSH	1350	-1358				
DISP. RATE 5 BPM	MIX	1358	-1442				
SLURRY VOL 1.32 FT <sup>3</sup> /SK	CHANGE VALUES	1442	-1445				
SLURRY WT 14.8-15 PPG	DISPLACE	1445	-1500				
WATER/CEMENT 6.25 GAL/SK	FINAL LFT 460	PSI					
WATER TEMP 58 °F	PLUG LANDED @	480	PSI				
	TOTAL SLURRY VOL	176	BRL CEMENT				
Remarks	PREFLUSH w/ 30 BBL H <sub>2</sub> O	Tax Reference Code	Sub Total				
	DISPLACE w/ 72.5 BRL H <sub>2</sub> O	State CO 2.9 %	Tax				
	CIRCULATE 4 BRL CEMENT	Disc.	Total				
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		64			
1216/1217		Bulk Truck		64			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Joe, Josh, KERRY

Received By *F. Jell*

Customer or His Agent