



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198788

Date 12-23-10	Well Owner KERR MCGEE	Well No. 30-3	Lease WINTERS
County WELD	State COLORADO	Field	
Charge to KERR MCGEE OIL & GAS ONSHORE, LP			Charge Code
Address 1999 BROADWAY, SUITE 3700 (XTREME-6)			For Office Use Only
City, State DENVER, COLORADO 80202			
Pump Truck No. 1202	Code	Bulk Truck No. 1214/1216	Code
Type of Job	Depth	Fl. 565	To
Surface 8 5/8" CS4-24#	Bottom of Surface	Fl. 550	To
Plug	Plug Landed @ 506	Fl. Time On 13:15	
Production	Pipe Landed @ 550	Fl. Time Off	PLUG DOWN 2200

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat TYPE III 100% EXCESS	350	SKS		
	Poz. Mix				
	Calcium Chloride	2.5%			
	Gel % Flo-Cele 1/4 per Sack				
	Handling Charge				
	Hauling Charge				
	Additional Cement TOP OFF	40	SKS	14.40	
MIX RATE 4 BPM	PREFLUSH	2124	MIKE LINGREEN		
DISP RATE 5 BPM	MIX	2129	2129		
SLURRY VOL 1.32 FT³/SK	CHANGE VALVES	2150	2153		
SLURRY WT 14.8-15 PPG	DISPLACE	2153	2300		
WATER/CEMENT 62.5 GAL/SK	FINAL LEFT	230	PSI	800.12090	
WATER TEMP 60°F	PLUG LANDED @	250	PSI		
	TOTAL SLURRY VOL	91.5	BBL CEMENT		

Remarks PREFLUSH W/20 BBL H2O	Tax Reference Code	Sub Total
DISPLACE W/ 32 BBL H2O	State CO 2.9%	Tax
CIRCULATE 3 BBL CEMENT	Disc.	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other
1202		Pump Truck		6		
1214/1216		Bulk Truck		6		

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JOE, JOSH, KERRY, EVAN**

Received By

Customer or His Agent