

**FORM
5**Rev
02/08State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

1637977

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120 4. Contact Name: CINDY VUE
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6000
3. Address: P O BOX 173779 Fax: (720) 929-7461
City: DENVER State: CO Zip: 80217-37

5. API Number 05-123-30407-00 6. County: WELD
7. Well Name: PIONEER Well Number: 37-2
8. Location: QtrQtr: SESE Section: 2 Township: 2N Range: 65W Meridian: 6
Footage at surface: Distance: 644 feet Direction: FSL Distance: 660 feet Direction: FEL
As Drilled Latitude: _____ As Drilled Longitude: _____

GPS Data:

Data of Measurement: _____ PDOP Reading: _____ GPS Instrument Operator's Name: _____

** If directional footage

at Top of Prod. Zone Distance: 38 feet Direction: FSL Distance: 1296 feet Direction: FEL
Sec: 2 Twp: 2N Rng: 65W
at Bottom Hole Distance: 26 feet Direction: FSL Distance: 1296 feet Direction: FEL
Sec: 2 Twp: 2N Rng: 65W

9. Field Name: WATTENBERG 10. Field Number: 90750

11. Federal, Indian or State Lease Number: _____

12. Spud Date: (when the 1st bit hit the dirt) 12/15/2009 13. Date TD: 12/20/2009 14. Date Casing Set or D&A: 12/21/2009

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation16. Total Depth MD 7815 TVD 7730 17 Plug Back Total Depth MD 7767 TVD 768218. Elevations GR 4848 KB 4865

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CD-CN-ML, DG-SP-GR, CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8		0	855	600	0	855	CALC
1ST	7+7/8	4+1/2		0	7,801	270	6,130	7,801	CBL

ADDITIONAL CEMENT

Cement work date: _____

Details of work: _____

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	SURF	4,914	600	700	4,920
DV TOOL	1ST	7,801	600	6,130	7,801
STAGE TOOL	1ST	4,898	600	910	4,942

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	3,996	4,180	<input type="checkbox"/>	<input type="checkbox"/>	SURFACE: 855
SUSSEX	4,343	4,624	<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	6,885		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,147		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,175		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	7,627		<input type="checkbox"/>	<input type="checkbox"/>	

Comment: _____

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CINDY VUE

Title: REGULATORY ANALYST Date: 1/13/2010 Email: CINDY.VUE@ANADARKO.COM

Based on the information provided herein, this Drilling Completion Report (Form 5) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 6/21/2010

Attachment Check List

Att Doc Num	Name
1543867	CEMENT BOND LOG
1543868	GAMMA RAY
1543869	DENSITY/NEUTRON
1637977	DRILLING COMPLETION REPORT
1637980	DIRECTIONAL SURVEY
1637981	CEMENT JOB SUMMARY

Total Attach: 6 Files

General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)