



02054893



State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 (303) 894-2100 Fax: (303) 894-2109

**RECEIVED**

FEB 15 2011

COGCC**LOSS OF WELL CONTROL REPORT**

As required by Rule 327.

1. OGCC Operator Number: 100185	4. Contact Name & Phone DeAnne Spector
2. Name of Operator: Encana Oil & Gas (USA) Inc	Ph: 720-876-5826
3. Address: 370 17th St STE 1700	Fax: 720-876-6826
City: Denver State: CO Zip: 80202-5632	

Report taken by:

DAVE ANDREWS

WELL LOCATION INFORMATION

5. API Number: 05-045-20261-00	6. County: Garfield
7. Well Name: Benjamin Federal	8. Well Number: 33-3B (K28NW)
9. Unit Name (if appl.): Grass Mesa	10. Unit No: COC056608 X
11. QtrQtr: NESW Sec: 28 Twp: 6S Rng: 93W Meridian: 6	
12. Footage From Exterior Section Lines: 1568' FSL and 2431' FWL	
13. Field Name: Mamm Creek	14. Field Number: 52500

CASING INFORMATION

15. Surface Casing Size: 9-5/8" / Weight per Foot: 36 Grade: J55 True Vertical Setting Depth: 1498
16. Intermed. Casing Size: / Weight per Foot: Grade: True Vertical Setting Depth:

KICK INFORMATION

17. True Vertical Depth at Kick: 9684'	19. Formation Code: CRCRN
18. Formation at Kick: Corcoran	
20. Shut-in Drill Pipe Pressure (SIDPP): 79 psi	
21. Shut-in Casing Pressure (SICP): 340 psi	
22. Mud Weight at Time of Kick: 13 ppG	
23. Pit Gain: 44 bbls.	
24. Time and Date Shut In: 22:30 hrs on 2/14/11	
25. Mud Weight Required to Control Well: 13.1 ppG	
26. Type of Kick: <input checked="" type="checkbox"/> Gas <input type="checkbox"/> Oil <input type="checkbox"/> Water	
27. Comments (describe actions to control in detail):	
While circulating on bottom after wiping hole, too 44 bbl gain. Well was shut in @ 22:30 hrs on 2/14/11 with a recorded SIDPP of 79 psi and SICP of 340 psi. Began to circulate influx out @ 40 SPM @ 13.1 MW. Influx was circulated out with 1 bottoms up @ 2:00 AM on 2/15/11.	