

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400132346

Plugging Bond Surety

20100210

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☐ COALBED ☒ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: \_\_\_\_\_

4. COGCC Operator Number: 100264

5. Address: \_\_\_\_\_

City: \_\_\_\_\_ State: NM Zip: 87410

6. Contact Name: Kelly Kardos Phone: (505)333-3145 Fax: (505)213-0546

Email: kelly\_kardos@xtoenergy.com

7. Well Name: GOLDEN EAGLE Well Number: 30-08

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 2346

WELL LOCATION INFORMATION

10. QtrQtr: SENE Sec: 30 Twp: 33S Rng: 67W Meridian: 6

Latitude: 37.144707 Longitude: -104.922120

Footage at Surface: 2132 feet FNL/FSL FNL 1060 feet FEL/FWL FEL

11. Field Name: PURGATOIRE RIVER Field Number: 70830

12. Ground Elevation: 7721 13. County: LAS ANIMAS

14. GPS Data:

Date of Measurement: 11/18/2010 PDOP Reading: 6.0 Instrument Operator's Name: GARY TERRY

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_

Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_ Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 2230 ft

18. Distance to nearest property line: 2132 ft 19. Distance to nearest well permitted/completed in the same formation: 1420 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
RATON	RTON			
VERMEJO	VRMJ			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☐ Fee ☒ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
See attached.....

25. Distance to Nearest Mineral Lease Line: 4220 ft 26. Total Acres in Lease: 5710

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: BURY/HAUL

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	17+1/2	13+3/8	54		45	98	45	0
SURF	11	8+5/8	24		1,025	670	1,025	0
1ST	7+7/8	5+1/2	15.5		2,346	100	2,346	1,613
			Stage Tool		1,613	250	1,613	0

32. BOP Equipment Type: ☐ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments Water well (DOW AC1) is located within one mile of the proposed location

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Kelly K. Kardos

Title: Sr. Permitting Tech Date: \_\_\_\_\_ Email: kelly\_kardos@xtoenergy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

<b>API NUMBER</b>  05	Permit Number: _____	Expiration Date: _____
	<b>CONDITIONS OF APPROVAL, IF ANY:</b>	

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

--

**Attachment Check List**

Att Doc Num	Name
400132355	PLAT
400132356	CONSULT NOTICE
400132357	TOPO MAP
400132358	LEASE MAP
400132359	SURFACE AGRMT/SURETY
400132360	WAIVERS
400132361	PROPOSED BMPs

Total Attach: 7 Files

**General Comments**

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

**BMP**

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)