



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198651

Date	11-13-10	Well Owner	KERR MCGEE	Well No.	7-27	Lease	DRY CREEK
County	WELD	State	COLORADO			Field	
Charge to	KERR MCGEE OIL + GAS ONSHORE, LP					Charge Code	
Address	1999 BROADWAY, SUITE 3700 (XTREME-12)					Fur Office Use Only	
City, State	DENVER COLORADO 80202						
Pump Track No.	1202	Code		Bulk Track No.	1217/1218	Code	
Type of Job		Depth		Fl.	1175	To	
Surface	8 7/8" CGS-244	Bottom of Surface		Fl.	1166	To	
Plug		Plug Landed @	1122	Fl.	Time On	2300	
Production		Pipe Landed @	1166	Fl.	Time Off	PLUG DOWN 0745	

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Track Charge				
	Cement Nuts - TYPE III 100% G/CESS	730	SKS	MIKE LINGREEN	
	Poz. Mix			USE 10 1/2" O.D.	
	Calcium Chloride	2.5%			
	Gel % Flo-Cele 1/4 per Sack			WBS 10 1/2" O.D.	2036490.00
	Handling Charge			80012090	
	Hauling Charge				
	Additional Cement	60	SKS		

MIX RATE 4 BPM	PREFLUSH	0634	0642		
DISP. RATE 5 BPM	MIX	0642	0728		
SLURRY VOL 1.33 FT ³ /SK	CHARGE VALVES	0728	0731		
SLURRY WT 14.8-15 PPG	DISPLACE	0731	0745		
WATER/CEMENT 6.25 GAL/SK	FWBL LIFT	500	PSI		
WATER TEMP 80° F	PLUG LAXED @	700	PSI		
	TOTAL SLURRY VOL	185.5	BBL	CEMENT	

Remarks: PREFLUSH W/ 30 BBL H ₂ O	Tax Reference Code	Sub Total
DISPLACE W/ 71 BBL H ₂ O	State CO 2.9 %	Tax
CIRCULATE 3 BBL CEMENT	Disc.	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		66			
1217/1218		Bulk Truck		66			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Joe, Josh, KERRY

Received By

M. Beele

Customer or His Agent