

FORM  
5  
Rev  
02/08

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

DRILLING COMPLETION REPORT

Document Number:

2509228

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type  Final completion  Preliminary completion

1. OGCC Operator Number: 28700 4. Contact Name: JACKIE DAVIS  
2. Name of Operator: EXXON MOBIL OIL CORPORATION Phone: (281) 654-1913  
3. Address: P O BOX 4358 WGR RM 310 Fax: (281) 654-1940  
City: HOUSTON State: TX Zip: 77210-43

5. API Number 05-103-11089-00 6. County: RIO BLANCO  
7. Well Name: PICEANCE CREEK UNIT Well Number: 197-34B9  
8. Location: QtrQtr: SESE Section: 34 Township: 1S Range: 97W Meridian: 6  
Footage at surface: Distance: 802 feet Direction: FSL Distance: 959 feet Direction: FEL  
As Drilled Latitude: 39.915594 As Drilled Longitude: -108.261183

GPS Data:

Data of Measurement: 04/15/2010 PDOP Reading: 3.2 GPS Instrument Operator's Name: D. PETTY

\*\* If directional footage

at Top of Prod. Zone Distance: 337 feet Direction: FNL Distance: 2550 feet Direction: FEL  
Sec: 3 Twp: 2s Rng: 97w  
at Bottom Hole Distance: 519 feet Direction: FNL Distance: 2656 feet Direction: FEL  
Sec: 3 Twp: 2s Rng: 97w

9. Field Name: PICEANCE CREEK 10. Field Number: 68800  
11. Federal, Indian or State Lease Number: COD-035729

12. Spud Date: (when the 1st bit hit the dirt) 12/17/2008 13. Date TD: 01/15/2010 14. Date Casing Set or D&A: 01/18/2010

15. Well Classification:

Dry  Oil  Gas/Coalbed  Disposal  Stratigraphic  Enhanced Recovery  Storage  Observation

16. Total Depth MD 12940 TVD 12542 17 Plug Back Total Depth MD 12940 TVD 12542

18. Elevations GR 6638 KB 6651

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CORRELATION GR/CCL, RESERVOIR PERFORMANCE MONITOR GASVIEW SATURATION ANALYSIS, RADIAL ANALYSIS MUD, RESERVOIR PERFORMANCE MONITOR, IMAGING BEHIND CASING ULTRASONIC TOOL GR/CCL, PERFORM-DIG MECHANICS, DIRECTIONAL SURVEYS, CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16		0	120	96	0	120	CALC
SURF	14+3/4	10+3/4		0	3,980	1,160	1,303	3,980	CALC
1ST	9+7/8	7		0	8,888	1,310	3,500	8,888	CALC
2ND	6+1/8	4+1/2		0	12,940	905	6,550	12,940	CBL

ADDITIONAL CEMENT

Cement work date: \_\_\_\_\_

Details of work:

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	SURF	1,303	745	0	1,303

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH G	5,720	6,090	<input type="checkbox"/>	<input type="checkbox"/>	
FORT UNION	6,090	7,520	<input type="checkbox"/>	<input type="checkbox"/>	
OHIO CREEK	7,520	8,070	<input type="checkbox"/>	<input type="checkbox"/>	
WILLIAMS FORK - CAMEO	8,070	11,660	<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	11,660	11,870	<input type="checkbox"/>	<input type="checkbox"/>	
COZZETTE	11,870	12,140	<input type="checkbox"/>	<input type="checkbox"/>	
CORCORAN	12,140	12,940	<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

RESUBMITTED TO SHOW TOP OF PRD ZONE AND BOTTOM HOLE FOOTAGES.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: JACKIE DAVIS

Title: SUPPORT STAFF TECH ASST Date: 7/7/2010 Email: JACKIE.P.DAVIS@EXXONMOBIL.COM

**Attachment Check List**

Att Doc Num	Name
2509228	FORM 5 SUBMITTED

Total Attach: 1 Files

**General Comments**

User Group	Comment	Comment Date
Permit	Req logs scanned in 11/24/10, req RA bond with final form 5	11/29/2010 2:21:25 PM
Permit	Requested hard copies of all logs except MUD	11/16/2010 8:35:14 AM

Total: 2 comment(s)