

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refilling ☐
Sidetrack ☐

Document Number:

400127105

Plugging Bond Surety

20090078

3. Name of Operator: PETROLEUM DEVELOPMENT CORPORATION

4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO Zip: 80203

6. Contact Name: Liz Lindow Phone: (303)590-8789 Fax: ()

Email: llindow@petd.com

7. Well Name: Wilson Well Number: 24-30H

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 11109

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 30 Twp: 7N Rng: 63W Meridian: 6

Latitude: 40.537800 Longitude: -104.484350

Footage at Surface: 150 feet FNL/FSL FSL 1350 feet FEL/FWL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4772 13. County: WELD

14. GPS Data:

Date of Measurement: 12/12/2010 PDOP Reading: 1.1 Instrument Operator's Name: Brian T. Brinkman

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 922 FSL 1331 FWL 500 FNL 1320 FWL 500
Sec: 60 Twp: 7N Rng: 63W Sec: 30 Twp: 7N Rng: 63W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1340 ft

18. Distance to nearest property line: 150 ft 19. Distance to nearest well permitted/completed in the same formation: 493 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR		320	W/2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
W/2 of Section 30 T7N 63W

25. Distance to Nearest Mineral Lease Line: 500 ft 26. Total Acres in Lease: 320

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Closed Loop

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	500	200	500	0
1ST	8+3/4	7	26	0	7,678	809	6,539	600
1ST LINER	6+1/8	4+1/2	11.6	0	11,109			

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used. Operator requests approval of a Rule 318Aa, Rule 318Ac, Rule 318Ae and Rule 603a2 exception location: Welhead is to be located outside of a GWA drilling window, will be located more than 50' from an existing well head, is located 150' feet from the nearest property line, and requests approval of proposed spacing unit for the W2 of Section 30. Waivers and proposed spacing unit is attached. Well will tie to a tank battery facility onsite.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Liz Lindow

Title: Permit Representative Date: 1/26/2011 Email: llindow@petd.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 2/27/2011

Permit Number: _____ Expiration Date: 2/26/2013

API NUMBER

05 123 33024 00

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Note surface casing setting depth change from 400' to 500'. Increase cement coverage accordingly and cement to surface.

- 1) Provide 24 hr notice of spud to Bo Brown at 970-330-6085 or email at bo.brown@state.co.us.
- 2) Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC.
- 3) If completed, provide cement coverage from the intermediate casing shoe to a minimum of 200' above Niobrara. Verify cement with a cement bond log.
- 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
400127105	FORM 2 SUBMITTED
400127969	DEVIATED DRILLING PLAN
400127970	WELL LOCATION PLAT
400127971	TOPO MAP
400127973	30 DAY NOTICE LETTER
400127974	EXCEPTION LOC WAIVERS
400127976	EXCEPTION LOC WAIVERS
400127978	EXCEPTION LOC WAIVERS
400128029	EXCEPTION LOC REQUEST
400128035	PROPOSED SPACING UNIT

Total Attach: 10 Files

General Comments

User Group	Comment	Comment Date
Permit	Opr corrected. kk	1/28/2011 3:10:30 PM
Permit	back to draft status mud disposal question left unanswered. kk	1/27/2011 4:02:45 PM

Total: 2 comment(s)

BMP

Type	Comment

Total: 0 comment(s)