

Facilities List

SG B36 496

Drilling

- 33 Wells – one will be for injection only
- 1 Steel cuttings bin
- 4 Water tanks
- 6 Electric motors
- 1 Water pipeline
- 5 Gas or diesel motors
- 3 Electric generators
- 1 Flare stack and flare ditch
- 2 Fuel tanks

Completions

- 33 Wells – one will be for injection only
- 34 Water tanks total – will be on location for 90 days
- 1 Gas pipeline
- 1 Water line
- 1 Flare stack
- 32 Separators; on location for a span of 60 days during completion
- Gas or diesel motors:
 - Fracing – 13 on location for 4 weeks
 - Snubbing – 2 on location for 4 weeks
 - Coil tubing – 2 on location for 4 weeks
 - Water – 1 on location for 60 days

During Production

- 33 Wellheads – one for injection only
- 1 pigging station
- 2 Gas pipeline
- 4 Water tanks
- 1 Water pipeline
- 8 Meter houses
- 1 Injection/filtration Skid