

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐
Sidetrack ☐

Document Number:

400127046

Plugging Bond Surety

20030058

3. Name of Operator: EOG RESOURCES INC

4. COGCC Operator Number: 27742

5. Address: 600 17TH ST STE 1100N

City: DENVER State: CO Zip: 80202

6. Contact Name: Jennifer yu Phone: (303)824-5576 Fax: (303)824-5577
Email: jennifer_yu@eogresources.com

7. Well Name: Fiscus Mesa Well Number: 17-19H

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 10419

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 19 Twp: 9N Rng: 58W Meridian: 6

Latitude: 40.730614 Longitude: -103.899436

Footage at Surface: 501 feet FNL/FSL 501 feet FEL/FWL FEL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 4830 13. County: WELD

14. GPS Data:

Date of Measurement: 10/19/2010 PDOP Reading: 2.1 Instrument Operator's Name: Robert Kay

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 924 FSL 716 FEL 600 FEL/FWL 2634 FEL 600
Sec: 19 Twp: 9N Rng: 58W Sec: 19 Twp: 9N Rng: 58W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 5730 ft

18. Distance to nearest property line: 501 ft 19. Distance to nearest well permitted/completed in the same formation: 3280 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	535-3	640	ALL

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Please see attached lease description.

25. Distance to Nearest Mineral Lease Line: 600 ft 26. Total Acres in Lease: 4815

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Backfill and cover

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16	42	0	60	50	60	0
SURF	13+1/2	9+5/8	36	0	1,220	610	1,220	0
1ST	8+3/4	7	23	0	6,186	660	6,186	0
1ST LINER	6	4+1/2	11.6	5436	10,419	310	10,419	5,436

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments _____

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jennifer Yu

Title: Regulatory Admin. Date: 2/3/2011 Email: jennifer_yu@eogresources.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 3/3/2011

API NUMBER 05 123 33083 00	Permit Number: _____	Expiration Date: <u>3/2/2013</u>
--------------------------------------	----------------------	----------------------------------

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hr notice of MIRU to Colby Horton at 970-370-0040 or colby.horton@state.co.us.
- 2) Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC.
- 3) If completed, provide cement coverage from the intermediate casing shoe to a minimum of 200' above Niobrara. Verify cement with a cement bond log.
- 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
400127046	FORM 2 SUBMITTED
400127047	PLAT
400127048	TOPO MAP
400127049	DEVIATED DRILLING PLAN
400127050	DRILLING PLAN
400127051	LEGAL/LEASE DESCRIPTION

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)