

FORM  
2  
Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

2. TYPE OF WELL

OIL  GAS  COALBED  OTHER \_\_\_\_\_  
SINGLE ZONE  MULTIPLE ZONE  COMMINGLE ZONE

Refilling   
Sidetrack

Document Number:  
400128090  
Plugging Bond Surety  
20030058

3. Name of Operator: EOG RESOURCES INC 4. COGCC Operator Number: 27742

5. Address: 600 17TH ST STE 1100N  
City: DENVER State: CO Zip: 80202

6. Contact Name: Kaylene Gardner Phone: (435)781-9111 Fax: (435)789-7633  
Email: Kaylene\_Gardner@eogresources.com

7. Well Name: Fiscus Mesa Well Number: 15-17H

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 10276

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 17 Twp: 9N Rng: 58W Meridian: 6  
Latitude: 40.745272 Longitude: -103.888994

Footage at Surface: 501 feet FNL/FSL FSL 2412 feet FEL/FWL FWL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 4868 13. County: WELD

14. GPS Data:

Date of Measurement: 10/22/2010 PDOP Reading: 1.4 Instrument Operator's Name: Robert Kay

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 942 FSL FSL 2226 FEL/FWL FWL Bottom Hole: FNL/FSL 600 FNL 600 FEL/FWL FWL  
Sec: 17 Twp: 9N Rng: 58W Sec: 17 Twp: 9N Rng: 58W

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 5993 ft

18. Distance to nearest property line: 834 ft 19. Distance to nearest well permitted/completed in the same formation: 5810 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	535-3	640	ALL

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: \_\_\_\_\_

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bon  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
Please see attached lease description.

25. Distance to Nearest Mineral Lease Line: 600 ft 26. Total Acres in Lease: 4368

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?  Yes  No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)?  Yes  No

31. Mud disposal:  Offsite  Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method:  Land Farming  Land Spreading  Disposal Facility Other: Backfill and cover

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16	42	0	60	50	60	0
SURF	13+1/2	9+5/8	36	0	800	420	800	0
1ST	8+3/4	7	23	0	6,178	655	6,178	0
1ST LINER	6	4+1/2	11.6	5428	10,276	300	10,276	5,428

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None

33. Comments Spacing application has been filed.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ?  Yes  No

36. Is this application part of submitted Oil and Gas Location Assessment ?  Yes  No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Kaylene Gardner

Title: Sr. Regulatory Admin. Date: 2/3/2011 Email: Kaylene\_Gardner@eogresourc

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 3/3/2011

**API NUMBER**  
05 123 33087 00

Permit Number: \_\_\_\_\_ Expiration Date: 3/2/2013

**CONDITIONS OF APPROVAL, IF ANY:** \_\_\_\_\_

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

PROPOSED HORIZONTAL WELL BORE IS TO BE DRILLED INTO UNLEASED FEDERAL MINERALS. OPERATOR DISCUSSION WITH BLM REQUIRED: UNLEASED FEDERAL MINERALS CANNOT BE DRILLED UPON/PRODUCED REGARDLESS OF SPACING ORDER: REQUIRED SETBACKS TO BE MAINTAINED---INTERAGENCY DISCUSSION PURSUANT TO MOU COGCC,BLM,USFS 6-24-09 H.2.d

- 1) Provide 24 hr notice of MIRU to Colby Horton at 970-370-0040 or colby.horton@state.co.us.
- 2) Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC.
- 3) If completed, provide cement coverage from the intermediate casing shoe to a minimum of 200' above Niobrara. Verify cement with a cement bond log.
- 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### Attachment Check List

Att Doc Num	Name
400128090	FORM 2 SUBMITTED
400128167	DEVIATED DRILLING PLAN
400128168	DRILLING PLAN
400128170	PLAT
400128171	TOPO MAP
400128985	LEGAL/LEASE DESCRIPTION

Total Attach: 6 Files

### General Comments

User Group	Comment	Comment Date
OGLA	On Hold Lateral passed thru Fed minerals which appear to be unleased.	2/7/2011 12:07:55 PM

Total: 1 comment(s)

### BMP

Type	Comment

Total: 0 comment(s)