

CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198662



Date <u>11/16/2010</u>	Well Owner <u>KERR/McGEE</u>	Well No. <u>9-33</u>	Lease <u>COTTONWOOD</u>
County <u>WELD</u>	State <u>COLORADO</u>	Field	
Charge to <u>KERR/McGEE OIL & GAS ONSHORE, LP</u>	Charge Code		For Office Use Only
Address <u>999 BROADWAY STE. 3700 (PATTERSON #189)</u>			
City, State <u>DENVER, COLORADO 80202</u>			
Pump Truck No. <u>1201</u>	Code	Bulk Truck No. <u>1218/1218</u>	Code
Type of Job	Depth	Ft. <u>1002</u>	To
Surface <u>8 5/8" CSG 24"</u>	Bottom of Surface	Ft. <u>992</u>	To
Plug	Plug Landed @ <u>948</u>	Ft. Time On <u>2330</u>	
Production	Pipe Landed @ <u>992</u>	Ft. <u>Time Off</u>	<u>Time Down 0315</u>

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Nxt TYPE III	620	SKS		
	Poz. Mix				
	Calcium Chloride	2.5	BALE LINKEEN		
	Gel % Flo-Cele 1/4 Per Sack		User ID ZMDLG		
	Handling Charge		WBS/MOICC	2010426.PRL	
	Hauling Charge		G/L Acct.	00012040	
	Additional Cement				
	MIXING RATE 4BPM		PRE-FLUSH	0226-0232	
	DISP RATE 5 BPM		MIX	0232-0300	
	SLURRY VOL 1.32 CU FT/SK		CHANGE VALVES	0300-0303	
	SLURRY WT 14.8-15.0 PPG		DISPLACE	0303-0315	
	WATER/CEMENT 6.25 GAL/SK		FINAL LIFT	520	
	TOTAL SLURRY VOL 145.5 BBLS CEMENT				
	PLUG LANDED @ 510 PSI				
	WATER TEMP 54				
	PRE-FLUSH 1/30 BBLS H ₂ O		Tax Reference Code	Sub Total	
	DISPLACE 1/60 BBLS H ₂ O		State <u>002.9%</u>	Tax	
	CIRCULATE 3 BBLS CEMENT		Disc.	Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		68			
1214/1218		Bulk Truck		68/68			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim/Sam/Oscar/Travis

Received By Sheryl Harrison
Customer or His Agent