

FORM
5Rev
02/08State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400139305

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100185

4. Contact Name: Heather Mitchell

2. Name of Operator: ENCANA OIL & GAS (USA) INC

Phone: (720) 876-3070

3. Address: 370 17TH ST STE 1700

Fax: (720) 876-4070

City: DENVER State: CO Zip: 80202-56

5. API Number 05-045-18864-00

6. County: GARFIELD

7. Well Name: SHIDELER

Well Number: 30-13A (C31E)

8. Location: QtrQtr: NENW Section: 31 Township: 7S Range: 92W Meridian: 6

Footage at surface: Distance: 249 feet Direction: FNL Distance: 538 feet Direction: FWL

As Drilled Latitude: 39.409296 As Drilled Longitude: -107.712220

GPS Data:

Data of Measurement: 09/07/2010 PDOP Reading: 2.0 GPS Instrument Operator's Name: Brandon Birdsall

** If directional footage

at Top of Prod. Zone Distance: 868 feet Direction: FSL Distance: 966 feet Direction: FWL

Sec: 30 Twp: 7S Rng: 96W

at Bottom Hole Distance: 876 feet Direction: FSL Distance: 1002 feet Direction: FWL

Sec: 30 Twp: 7S Rng: 96W

9. Field Name: MAMM CREEK

10. Field Number: 52500

11. Federal, Indian or State Lease Number: COC055972E

12. Spud Date: (when the 1st bit hit the dirt) 05/03/2010 13. Date TD: 05/27/2010 14. Date Casing Set or D&A: 05/27/2010

15. Well Classification:

☐ Dry ☐ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8181 TVD 8120 17 Plug Back Total Depth MD 8039 TVD 7978

18. Elevations GR 6750 KB 6772

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

RST, CBL and Mud

20. Casing, Liner and Cement:

CASING

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Top | Cmt Bot | Status |
|-------------|--------------|----------------|-----------|---------------|---------------|-----------|---------|---------|--------|
| CONDUCTOR | 26 | 16 | Line pipe | 0 | 62 | | 0 | 40 | CALC |
| SURF | 12+1/4 | 9+5/8 | 36 | 0 | 1,011 | 347 | 0 | 1,011 | CALC |
| 2ND | 8+3/4 | 4+1/2 | 12 | 0 | 8,174 | 1,131 | 2,810 | 8,174 | CBL |

ADDITIONAL CEMENT

Cement work date: _____

Details of work:

| Method used | String | Cementing tool setting/pref depth | Cement volume | Cement top | Cement bottom |
|-------------|--------|-----------------------------------|---------------|------------|---------------|
| | | | | | |

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

| FORMATION NAME | Measured Depth | | Check if applies | | COMMENTS (All DST and Core Analyses must be submitted to COGCC) |
|----------------|----------------|--------|--------------------------|--------------------------|---|
| | Top | Bottom | DST | Cored | |
| WILLIAMS FORK | 5,180 | 8,172 | <input type="checkbox"/> | <input type="checkbox"/> | |
| ROLLINS | 8,173 | 8,181 | <input type="checkbox"/> | <input type="checkbox"/> | |

Comment:

RST and CBL are contained in the same las document. All logs were uploaded using the file upload application. Uploading them via eforms was locking up the form. TOG: 5972'

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Heather Mitchell

Title: Regulatory Analyst

Date:

Email: heather.mitchell@encana.com

Attachment Check List

| Att Doc Num | Name |
|-------------|--------------------|
| 400139308 | DIRECTIONAL SURVEY |
| 400139309 | CEMENT JOB SUMMARY |

Total Attach: 2 Files

General Comments

| <u>User Group</u> | <u>Comment</u> | <u>Comment Date</u> |
|-------------------|----------------|---------------------|
| | | |

Total: 0 comment(s)