

**FORM  
5**Rev  
02/08State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

2554632

**DRILLING COMPLETION REPORT**

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120 4. Contact Name: CINDY VUE  
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6832  
3. Address: P O BOX 173779 Fax: (720) 929-7832  
City: DENVER State: CO Zip: 80217-37

5. API Number 05-123-29453-00 6. County: WELD  
7. Well Name: SEC FOUR Well Number: 6-4  
8. Location: QtrQtr: NWNW Section: 4 Township: 1N Range: 68W Meridian: 6  
Footage at surface: Distance: 1293 feet Direction: FNL Distance: 1257 feet Direction: FWL  
As Drilled Latitude: 40.084111 As Drilled Longitude: -105.013219

## GPS Data:

Data of Measurement: 09/08/2009 PDOP Reading: 2.3 GPS Instrument Operator's Name: CODY MATTSON

## \*\* If directional footage

at Top of Prod. Zone Distance: 1942 feet Direction: FNL Distance: 1963 feet Direction: FWL  
Sec: 4 Twp: 1N Rng: 68W  
at Bottom Hole Distance: 1934 feet Direction: FNL Distance: 1969 feet Direction: FWL  
Sec: 4 Twp: 1N Rng: 68W

9. Field Name: WATTENBERG 10. Field Number: 90750

11. Federal, Indian or State Lease Number: \_\_\_\_\_

12. Spud Date: (when the 1st bit hit the dirt) 06/12/2009 13. Date TD: 06/15/2009 14. Date Casing Set or D&A: 06/16/2009

## 15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation16. Total Depth MD 8465 TVD 8374 17 Plug Back Total Depth MD 8419 TVD 832818. Elevations GR 5027 KB 5042

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

## 19. List Electric Logs Run:

SBL, DIL/GL/GR, CDL/CNL/ML

## 20. Casing, Liner and Cement:

### CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8		0	819	520	0	819	CALC
1ST	7+7/8	4+1/2		0	8,452	730	3,752	8,452	CBL

### ADDITIONAL CEMENT

Cement work date: \_\_\_\_\_

Details of work: \_\_\_\_\_

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

21. Formation log intervals and test zones:

### FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	4,152		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,652		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	5,174		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,532		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,844		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,866		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	8,302		<input type="checkbox"/>	<input type="checkbox"/>	

Comment: \_\_\_\_\_

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: CINDY VUE

Title: REGULATORY Date: 5/20/2010 Email: CINDY.VUE@ANADARKO.COM

### Attachment Check List

Att Doc Num	Name
2072015	CEMENT JOB SUMMARY
2554632	FORM 5 SUBMITTED
2554633	DIRECTIONAL SURVEY
2554635	CEMENT JOB SUMMARY

Total Attach: 4 Files

### General Comments

User Group	Comment	Comment Date
Permit	request more legible copy of cement tkt	11/18/2010 12:08:28 PM

Total: 1 comment(s)