

FORM  
5A

Rev  
02/08

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400139791

**COMPLETED INTERVAL REPORT**

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 66571 4. Contact Name: Joan Proulx  
2. Name of Operator: OXY USA WTP LP Phone: (970) 263.3641  
3. Address: P O BOX 27757 Fax: (970) 263.3694  
City: HOUSTON State: TX Zip: 77227

5. API Number 05-045-18059-00 6. County: GARFIELD  
7. Well Name: CASCADE CREEK Well Number: 697-16-17A  
8. Location: QtrQtr: NWSW Section: 16 Township: 6S Range: 97W Meridian: 6  
9. Field Name: GRAND VALLEY Field Code: 31290

Completed Interval

FORMATION: WILLIAMS FORK - CAMEO Status: PRODUCING  
Treatment Date: 07/20/2010 Date of First Production this formation: 09/01/2010  
Perforations Top: 7120 Bottom: 8519 No. Holes: 186 Hole size: 35/100  
Provide a brief summary of the formation treatment: Open Hole: ☐  
7 stages of slickwater frac with 19,918 bbls of frac fluid and 747,134 lbs of 30/50 white sand proppant  
This formation is commingled with another formation: ☐ Yes ☒ No  
**Test Information:**  
Date: 09/02/2010 Hours: 24 Bbls oil: 0 Mcf Gas: 1704 Bbls H2O: 315  
Calculated 24 hour rate: Bbls oil: 0 Mcf Gas: 1704 Bbls H2O: 315 GOR: 0  
Test Method: Flowing Casing PSI: 1725 Tubing PSI: 1200 Choke Size: 20/64  
Gas Disposition: SOLD Gas Type: DRY BTU Gas: 1022 API Gravity Oil: 0  
Tubing Size: 2 + 3/8 Tubing Setting Depth: 8049 Tbg setting date: 08/30/2010 Packer Depth: \_\_\_\_\_  
Reason for Non-Production: \_\_\_\_\_  
Date formation Abandoned: \_\_\_\_\_ Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt \_\_\_\_\_  
Bridge Plug Depth: \_\_\_\_\_ Sacks cement on top: \_\_\_\_\_

Comment:

This Form 5A is being submitted to add the BTU data.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Joan Proulx

Title: Regulatory Analyst Date: \_\_\_\_\_ Email joan\_proulx@oxy.com

### Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

### General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)