



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198502

Date 10-11-10	Well Owner KERR MCGEE	Well No. 25-27	Lease DRY CREEK
County WELD	State COLORADO	Field	
Charge to KERR MCGEE OIL & GAS ONSHORE, LP	Charge Code		For Office Use Only
Address 1999 BROADWAY, SUITE 3700 (XTREME-12)			
City, State DENVER COLORADO 80202			
Pump Truck No. 1202	Code	Bulk Truck No. 1216/1217	Code
Type of Job	Depth	Fl. 1204	To
Surface 8 5/8" CSG - 34 #	Bottom of Surface	Fl. 1194	To
Plug	Plug Landed @ 1150	Fl. Time On 0300	
Production	Pipe Landed @ 1194	Fl. Time Off PLUG DOWN 1130	

Reference No.	Description	Qty.	Meas.	Unit Price	Amount		
	Pump Truck Charge						
	Cement Neat TYPE III	750	SKS				
	Poz. Mix						
	Calcium Chloride	2.5%					
	Gel % Flo-Cele 1/4 Per Sack		MIKE LINGREEN				
	Handling Charge		User ID 740 A				
	Hauling Charge		WBS/IN/CO 2036517 DRI				
	Additional Cement		GL Accr 800 12090				
MIX RATE	4 BPM	PREFLUSH	1020 - 1028				
DISP. RATE	5 BPM	MIX	1028 - 1112				
SLURRY VOL	1.32 FT ³ /SK	CHANGE VALUES	1112 - 1115				
SLURRY WT	14.8-15 PPG	DISPLACE	1115 - 1130				
WATER/CEMENT	6.25 GM/SK	FINAL LIFT 500	PSI				
WATER TEMP	68 °F	PLUG LANDED @	580 PSI				
		TOTAL SLURRY VOL	176	BBL CEMENT			
Remarks: PREFLUSH w/ 30 BBL H2O		Tax Reference Code	Sub Total				
DISPLACE w/ 73 BBL H2O		State CO 2.9 %	Tax				
CIRCULATE 7 BBL CEMENT		Disc.	Total				
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		64			
1216/1217		Bulk Truck		64			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **Joe, Josh, KERRY**

Received By **L. Jell**

Customer or His Agent