

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400144115

Plugging Bond Surety

20100210

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☐ COALBED ☒ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐
Sidetrack ☐

3. Name of Operator: XTO ENERGY INC

4. COGCC Operator Number: 100264

5. Address: 382 CR 3100

City: AZTEC State: NM Zip: 87410

6. Contact Name: Kelly Kardos Phone: (505)333-3145 Fax: (505)213-0546

Email: kelly_kardos@xtoenergy.com

7. Well Name: APACHE CANYON Well Number: 20-03

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 2240

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 20 Twp: 34S Rng: 67W Meridian: 6

Latitude: 37.075179 Longitude: -104.915362

Footage at Surface: 668 feet FNL/FSL 1435 feet FEL/FWL
FNL FWL

11. Field Name: PURGATOIRE RIVER Field Number: 70830

12. Ground Elevation: 7725 13. County: LAS ANIMAS

14. GPS Data:

Date of Measurement: 01/28/2011 PDOP Reading: 6.0 Instrument Operator's Name: Gary Terry

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 2 mi

18. Distance to nearest property line: 1 mi 19. Distance to nearest well permitted/completed in the same formation: 1225 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
RATON	RTON			
VERMEJO	VRMJ			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☐ Fee ☒ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See Attached

25. Distance to Nearest Mineral Lease Line: 1 mi 26. Total Acres in Lease: 22317

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: BURY/HAUL

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	17+1/2	13+3/8	54	0	45	98	45	0
SURF	11	8+5/8	24	0	400	260	400	0
1ST	7+7/8	5+1/2	15.5	0	2,240	100	2,240	1,538
			Stage Tool		1,538	240	1,538	0

32. BOP Equipment Type: ☐ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments There is a water well within 1 mile of the proposed location. Add'l surf csg required.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kelly K. Kardos

Title: Sr. Permitting Tech Date: _____ Email: kelly_kardos@xtoenergy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

--

Attachment Check List

Att Doc Num	Name
400144124	PLAT
400144125	TOPO MAP
400144127	CONSULT NOTICE
400144128	PROPOSED BMPs
400144129	WAIVERS
400144130	LEASE MAP
400144131	SURFACE AGRMT/SURETY

Total Attach: 7 Files

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)

BMP

Type	Comment

Total: 0 comment(s)