



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198747

Date	12-11-10	Well Owner	KERR MCGEE	Well No.	18-5	Lease	WEIDEMAN
County	WELD	State	COLORADO			Field	
Charge to	KERR MCGEE OIL & GAS ONSHORE, LP					Charge Code	
Address	1999 BROADWAY, SUITE 3700 (XTREME-6)					For Office Use Only	
City, State	DENVER COLORADO 80202						
Pump Truck No.	1202	Code		Bulk Truck No.	1217/1218	Code	
Type of Job				Depth	827	To	
Surface	8 5/8" CSG - 244			Bottom of Surface	817	To	
Plug				Plug Landed @	773	Fl.	Time On 0930
Production				Pipe Landed @	817	Fl.	Time Off Plus 0000 1245

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Nxt TYPE III	520	SKS		
	Poz. Mix				
	Calcium Chloride	2.5%		204.3570000	
	Gel % Flo-Cele	4	#Per Sack	800.12090	
	Handling Charge				
	Hauling Charge				
	Additional Cement				
	MIX RATE 4 BPM	PREFLUSH	1156	1201	
	DEP. RATE 5 BPM	MIX	1201	1232	
	SLURRY VOL 1.32 FT ³ /SK	CHANGE VALUES	1232	1235	
	SLURRY WT 14.8-15 PPG	DISPLACE	1235	1245	
	WATER/CEMENT 6.25 GAL/SK	PLUG LANDED @	300	PSI	
	WATER TEMP 44 °F	FINAL LIFT	280	PSI	
		TOTAL SLURRY VOL	122	BBL CEMENT	

Remarks:	Tax Reference Code	Sub Total
PREFLUSH W/ 20 BBL H ₂ O		
DISPLACE W/ 49 BBL H ₂ O	State CO 2.9 %	Tax
CIRCULATE 60 BBL CEMENT	Disc.	Total

Track No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck					
1217/1218		Bulk Truck					

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOC, KERRY, EVAN

Received By *Mark Hake*
Customer or His Agent