



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198762

Date <u>12/12/2010</u>	Well Owner <u>KERR/McGEE</u>	Well No. <u>23-33</u>	Lease <u>COTTONWOOD</u>
County <u>WELD</u>	State <u>COLORADO</u>	Field	
Charge to <u>KERR/McGEE OIL & GAS ONSHORE LP</u>	Charge Code		For Office Use Only
Address <u>1999 BROADWAY STE 3700 (PATTERSON #189)</u>			
City, State <u>DENVER, COLORADO 80202</u>			
Pump Truck No. <u>1201</u>	Code	Bulk Truck No. <u>1214/1219</u>	Code
Type of Job	Depth	Fl. <u>1003</u>	To
Surface <u>8 5/8" CSG 24"</u>	Bottom of Surface	Fl. <u>993</u>	To
Plug	Plug Landed @ <u>949</u>	Fl. Time On <u>1400</u>	
Production	Pipe Landed @ <u>993</u>	Fl. Time Off <u>PLUG Landed 1630</u>	

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat TYPE III	630	SKS		
	Poz. Mix		MIKE LINGREEN		
	Calcium Chloride	2590			
	Gel % Flo-Cele 1/4 #Per Sack		User ID ZMDLB		
	Handling Charge		WBS/MOICC 2040334 DRL		
	Hauling Charge		G/L Acct. 90012090		
	Additional Cement				
	MIXING RATE 4 BPM		PRE-FLUSH	1541-1547	
	DISP RATE 5 BPM		MIX	1547-1615	
	SLURRY VOL 1.32 CU FT/SK		CHANGE VALVES	1615-1618	
	SLURRY WT 14.8-15.0 PPG		DISPLACE	1618-1630	
	WATER/CEMENT 6.25 GAL/SK		FINAL LIFT 435		
	TOTAL SLURRY VOL 148 BBLS CEMENT				
	PLUG LANDED @ 440 PSI				
	WATER TEMP 73				

Remarks: PRE-FLUSH 10/30 BBLS H ₂ O	Tax Reference Code	Sub Total
DISPLACE 10/60 BBLS H ₂ O	State CO 2.9 %	Tax
CIRCULATE 4 BBLS CEMENT	Disc.	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		60			
1214/1219		Bulk Truck		60/60			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM/SAM/OSCAR/TRAVIS

Received By Shirley Hawman
Customer or His Agent