

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission
1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

Document Number:

400097824

Plugging Bond Surety

20040071

3. Name of Operator: ANTERO RESOURCES PICEANCE CORPORATION 4. COGCC Operator Number: 10079

5. Address: 1625 17TH ST STE 300
City: DENVER State: CO Zip: 80202

6. Contact Name: Hannah Knopping Phone: (303)357-6412 Fax: (303)357-7315
Email: hknopping@anteroresources.com

7. Well Name: BAT Well Number: 34D-18-07-95

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 6390

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 18 Twp: 7S Rng: 95W Meridian: 6

Latitude: 39.431065 Longitude: -108.033243

Footage at Surface: 233 feet FSL 824 feet FEL
FNL/FSL FEL/FWL

11. Field Name: Parachute Field Number: 67350

12. Ground Elevation: 5441 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 09/17/2010 PDOP Reading: 3.0 Instrument Operator's Name: Elwood Barry Giles

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____
117 FSL 1960 FEL 117 FSL 1960 FEL
Sec: 18 Twp: 7S Rng: 95W Sec: 18 Twp: 7S Rng: 95W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 430 ft

18. Distance to nearest property line: 497 ft 19. Distance to nearest well permitted/completed in the same formation: 299 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	440-60	320	S/2

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached mineral lease map

25. Distance to Nearest Mineral Lease Line: 117 ft 26. Total Acres in Lease: 80

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: Land Farming Land Spreading Disposal Facility Other: Onsite if meet Tbl 910

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	55#		60	177	60	0
SURF	12+1/4	8+5/8	24/32#		2,200	834	2,200	0
1ST	7+7/8	4+1/2	11.6#		6,390	657	6,390	

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments First String/Production TOC will be >200 feet above Top of Gas. NOTE: Antero Resources (applicant) is the surface owner of the SESE of Section 18-T7S-R95W and a portion of the N2NENE of Section 19-T7S-R95W, where the subject well pad will be located and therefore no 30-Day Letter or SUA have been attached. #24-The well distance given is to a lease line within the drilling and spacing unit. BHL complies with spacing order with respect to distance to unit boundary.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Hannah Knopping

Title: Permit Representative Date: 10/27/2010 Email: hknopping@anteroresources.co

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 3/25/2011

Permit Number: _____ Expiration Date: 3/24/2013

API NUMBER

05 045 20533 00

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1.COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.
- 2.GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE
- 3.PRODUCTION CASING CEMENT TOP VERIFICATION BY CBL REQUIRED.
- 4.THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR THE ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 0 FEET DEEP.

Attachment Check List

Att Doc Num	Name
400097824	FORM 2 SUBMITTED
400097850	MINERAL LEASE MAP
400097851	WELL LOCATION PLAT
400102064	DEVIATED DRILLING PLAN
400104013	TOPO MAP

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Removed lles formation per HK.	11/9/2010 3:16:33 PM
Permit	ON HOLD. Requesting operator move BHL to comply with spacing order 200' from spacing unit boundary or submit a Request Exception Location letter and waiver. (Sec 19 spacing order 440-45 is 20 acre equal. Sec 19 spacing order 440-52 for 10 ac equal. for WMFK only.)	11/9/2010 2:20:34 PM

Total: 2 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)