

FORM
5A

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400148412

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120 4. Contact Name: CARA MAHLER
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6029
3. Address: P O BOX 173779 Fax: (720) 929-7029
City: DENVER State: CO Zip: 80217-37

5. API Number 05-123-31343-00 6. County: WELD
7. Well Name: NRC Well Number: 16-9
8. Location: QtrQtr: SWSE Section: 9 Township: 1N Range: 67W Meridian: 6
9. Field Name: _____ Field Code: _____

Completed Interval

FORMATION: NIOBRARA-CODELL Status: PRODUCING

Treatment Date: 03/08/2011 Date of First Production this formation: 03/11/2011
Perforations Top: 7542 Bottom: 7790 No. Holes: 114 Hole size: 0.42

Provide a brief summary of the formation treatment: _____ Open Hole: ☐

NB PERF 7542-7642 HOLES 60 SIZE .42 CD PERF 7772-7790 HOLES 54 SIZE .38
Frac Niobrara B & C down 4-1/2" Csg w/ 252 gal 15% HCl & 239,946 gal Slickwater w/ 201,980# 40/70, 4,000# SB Excel.
Frac Codell down 4-1/2" Csg w/ 191,646 gal Slickwater w/ 150,980# 40/70, 4,000# SB Excel.

This formation is commingled with another formation: ☐ Yes ☒ No

Test Information:

Date: 03/25/2011 Hours: 24 Bbls oil: 61 Mcf Gas: 25 Bbls H2O: 0
Calculated 24 hour rate: _____ Bbls oil: 61 Mcf Gas: 25 Bbls H2O: 0 GOR: 410
Test Method: FLOWING Casing PSI: 1450 Tubing PSI: _____ Choke Size: 12/64
Gas Disposition: SOLD Gas Type: WET BTU Gas: 1168 API Gravity Oil: 45
Tubing Size: _____ Tubing Setting Depth: _____ Tbg setting date: _____ Packer Depth: _____

Reason for Non-Production: _____

Date formation Abandoned: _____ Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt _____

Bridge Plug Depth: _____ Sacks cement on top: _____

Comment: _____

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: CARA MAHLER

Title: REGULATORY ANALYST 1

Date: _____

Email CARA.MAHLER@ANADARKO.COM

:

Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)