

IMPORTANT: SOME DATA FIELDS HAVE BEEN MODIFIED.

21. Mineral Ownership: Fee State Federal Indian Lease #: _____
22. Surface Ownership: Fee State Federal Indian
23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____
23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No
23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond
24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached Mineral Lease Description
25. Distance to Nearest Mineral Lease Line: 2960 ft 26. Total Acres in Lease: 9640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.
28. Will salt sections be encountered during drilling? Yes No
29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No
30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No
31. Mud disposal: Offsite Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**
Method: Land Farming Land Spreading Disposal Facility Other: _____
Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24+0/0	16+0/0	65	0	90	90	90	0
SURF	14+3/4	9+5/8	36	0	2,690	1,217	2,690	0
1ST	8+3/4	4+1/2	11.6	0	9,216	1,829	9,216	5,576

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None
33. Comments Oxy is both the surface and mineral owner; Rules 305 and 306 are waived . The well pad has been constructed and there is one producing well on this location. A semi-closed loop system will be used. Per GarCo Vacation Ordinance dated 10-5-1987, CR 213 is now OXY's private property north of Sec 8, 7S, 97W, 6 PM. Oxy will provide appropriate housing for essential personnel in order to conduct safe, efficient drilling operations at this well site. Oxy will comply with Notice to Operators (NTO) Drilling wells on the Roan Plateau (June 12, 2008).

34. Location ID: 335643
35. Is this application in a Comprehensive Drilling Plan ? Yes No
36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No
I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.
Signed: _____ Print Name: Joan Proulx
Title: Regulatory Analyst Date: 3/3/2011 Email: joan_proulx@oxy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 3/31/2011
Permit Number: _____ Expiration Date: 3/30/2013

API NUMBER

05 045 20584 00

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- (1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.
- (2) GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.
- (3) COMPLY WITH ALL PROVISIONS OF THE JUNE 12, 2008 NOTICE TO OPERATORS DRILLING WELLS WITHIN ¾ MILE OF THE RIM OF THE ROAN PLATEAU IN GARFIELD COUNTY -- PIT DESIGN, CONSTRUCTION, AND MONITORING REQUIREMENTS. SEE ATTACHED NOTICE.
- (4) THE NEARBY HILLSIDE MUST BE MONITORED FOR ANY DAY-LIGHTING DRILLING FLUIDS THROUGHOUT THE DRILLING OF THE SURFACE-CASING INTERVAL.
- (5) OPERATOR MUST ENSURE 110 PERCENT SECONDARY CONTAINMENT FOR ANY VOLUME OF FLUIDS CONTAINED AT WELL-SITE DURING DRILLING AND COMPLETION OPERATIONS. IF FLUIDS ARE CONVEYED VIA PIPELINE, OPERATOR MUST IMPLEMENT BEST-MANAGEMENT-PRACTICES TO CONTAIN ANY UNINTENTIONAL RELEASE OF FLUIDS.
- (6) THE SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 00 FEET DEEP.

Attachment Check List

Att Doc Num	Name
400138651	FORM 2 SUBMITTED
400138656	LEGAL/LEASE DESCRIPTION
400138657	WELL LOCATION PLAT
400138658	DEVIATED DRILLING PLAN
400138659	TOPO MAP

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)