



CEMENTER'S WELL SERVICE, INC.
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198791

Date <u>12/28/10</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>24-7</u>	Lease <u>Spaw</u>
County <u>Weld</u>	State <u>Colorado</u>	Field	
Charge to <u>Kerr McGee Oil & Gas Outshore, LP</u>	Charge Code		For Office Use Only
Address <u>1999 Broadway, Suite 3700 (Xtremeth)</u>			
City, State <u>Denver Colorado 80202</u>			
Pump Truck No. <u>1208</u>	Code	Bulk Truck No. <u>1317/1314</u>	Code
Type of Job	Depth	Fl. <u>776</u>	To
<u>Surface</u> <u>8 5/8" 350-24"</u>	Bottom of Surface	Fl. <u>767</u>	To
Plug	Plug Landed @ <u>733</u>	Fl. Time On <u>19:50</u>	
Production	Pipe Landed @ <u>767</u>	Fl. Time Off <u>Plug Down 0230</u>	

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Nod <u>✓ Type III</u>	480	SKS		
	Per. Mix				
	Calcium Chloride	2.5%			
	Gel % Flo-Cele $\frac{1}{4}$ #Per Sack				
	Handling Charge				
	Hauling Charge				
	Additional Cement				
	Mixing Rate - 4BPM	Pre-Flush	0151	0157	
	Disp Rate - 5BPM	Mixing	0157	0218	
	Slurry Vol - 1.32 cu ft/sk	Charge Valves	0218	0231	
	Slurry WT 14.8-15.0 #/sk	Disp	0231	0230	
	Water/Cement - 6.25 Gall/sk				
	Water Temp 60°F				
	Total Slurry Vol 113 BBS Cement				
	Landed Plug @ 400 PSI / Final LIFT @ 200 PSI				
Remarks: <u>Pre-Flush w/ 30 BBS H²O</u>	Tax Reference Code	Sub Total			
<u>Displace w/ 46 BBS H²O</u>	State <u>CO 2.9 %</u>	Tax			
<u>Circulate 6 BBS Cement</u>	Disc.	Total			

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>40</u>			
<u>1317/1314</u>		Bulk Truck		<u>40/40</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Dallas & James

Received By

Customer or His Agent

[Signature]

MIKE LINGREEN
User ID ZMDL6
MSGWVOC
R0391697