



Document Number:

400121076

Plugging Bond Surety

20010124

APPLICATION FOR PERMIT TO:

1. ☒ **Drill,** ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐
Sidetrack ☐

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP 4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: CHERYL LIGHT Phone: (720)929-6461 Fax: (720)929-7461

Email: CHERYL.LIGHT@ANADARKO.COM

7. Well Name: LEE Well Number: 28-6

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8021

WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 6 Twp: 2N Rng: 65W Meridian: 6

Latitude: 40.172914 Longitude: -104.704051

Footage at Surface: 646 feet FNL/FSL 2002 feet FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4962 13. County: WELD

14. GPS Data:

Date of Measurement: 08/26/2010 PDOP Reading: 1.9 Instrument Operator's Name: BEN MILIUS

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 50 FNL 2570 FEL 50 FNL 2570 FEL 50
Bottom Hole: FNL/FSL 50 FNL 2570 FEL 50
Sec: 6 Twp: 2N Rng: 65W Sec: 6 Twp: 2N Rng: 65W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 966 ft

18. Distance to nearest property line: 646 ft 19. Distance to nearest well permitted/completed in the same formation: 870 ft

20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| J SAND | JSND | | 160 | GWA |
| NIOBRARA- CODELL | NB-CD | 407-87 | 160 | GWA |

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
PLEASE SEE ATTACHED OIL AND GAS LEASE

25. Distance to Nearest Mineral Lease Line: _____ 50 ft 26. Total Acres in Lease: _____ 320

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

If 28, 29, or 30 are "Yes" a pit permit may be required.

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Btm | Cmt Top |
|-------------|--------------|----------------|-------|---------------|---------------|-----------|---------|---------|
| SURF | 12+1/4 | 8+5/8 | 24 | 0 | 800 | 560 | 800 | |
| 1ST | 7+7/8 | 4+1/2 | 11.6 | 0 | 8,021 | 200 | 8,021 | |

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED/ PROPOSED SPACING NB-CD AND JSND: SEC. 6: NW4NE4, NE4NW4, 3N-65W-31: SE4SW4, SW4SE4

34. Location ID: _____ 332306

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CHERYL LIGHT

Title: SENIOR REGULATORY ANALYST Date: 3/11/2011 Email: DJREGULATORY@ANADARK

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 4/6/2011

| | | |
|-------------------------------|----------------------|---------------------------|
| API NUMBER 05 123 33296 00 | Permit Number: _____ | Expiration Date: 4/5/2013 |
|-------------------------------|----------------------|---------------------------|

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

| Att Doc Num | Name |
|-------------|------------------------|
| 400121076 | FORM 2 SUBMITTED |
| 400121078 | WELL LOCATION PLAT |
| 400121079 | TOPO MAP |
| 400121080 | OIL & GAS LEASE |
| 400121081 | SURFACE AGRMT/SURETY |
| 400121082 | 30 DAY NOTICE LETTER |
| 400121083 | DEVIATED DRILLING PLAN |
| 400121084 | PROPOSED SPACING UNIT |

Total Attach: 8 Files

General Comments

| <u>User Group</u> | <u>Comment</u> | <u>Comment Date</u> |
|--------------------------|-----------------------|----------------------------|
| | | |

Total: 0 comment(s)

BMP

| <u>Type</u> | <u>Comment</u> |
|--------------------|-----------------------|
| | |

Total: 0 comment(s)