

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400139188

Plugging Bond Surety

20100017

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

3. Name of Operator: ENCANA OIL & GAS (USA) INC 4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700
City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Nick Curran Phone: (720)876-5288 Fax: (720)876-6288
Email: nick.curran@encana.com

7. Well Name: Ross Well Number: 12-19

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8124

WELL LOCATION INFORMATION

10. QtrQtr: SWNW Sec: 19 Twp: 2N Rng: 68W Meridian: 6

Latitude: 40.125690 Longitude: -105.052520

Footage at Surface: 1978 feet FNL 800 feet FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4988 13. County: WELD

14. GPS Data:

Date of Measurement: 10/13/2010 PDOP Reading: 1.9 Instrument Operator's Name: TOM WINANS

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: Twp: Rng: Sec: Twp: Rng:

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 765 ft

18. Distance to nearest property line: 3 ft 19. Distance to nearest well permitted/completed in the same formation: 969 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407-87	160	GWA
J SAND	JSND	232	160	GWA
NIOBRARA	NBRR	407-87	160	GWA

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T2N-R68W SEC 19 S2NW

25. Distance to Nearest Mineral Lease Line: 72 ft 26. Total Acres in Lease: 80

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	800	350	800	
1ST	7+7/8	4+1/2	11.6	0	8,124	280	8,124	7,056

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments NO CONDUCTOR CASING WILL BE USED.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: NICK CURRAN

Title: PERMITTING AGENT Date: 3/15/2011 Email: NICK.CURRAN@ENCANA.CO

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 4/8/2011

API NUMBER
05 123 33315 00

Permit Number: _____ Expiration Date: 4/7/2013

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
400139188	FORM 2 SUBMITTED
400141386	LEASE MAP
400141421	30 DAY NOTICE LETTER
400141422	SURFACE AGRMT/SURETY
400141423	TOPO MAP
400141424	WELL LOCATION PLAT
400141425	EXCEPTION LOC WAIVERS
400141428	EXCEPTION LOC REQUEST

Total Attach: 8 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Agency	Operator has requested an exception location request for Rule 603.a.(2) for proximity to a property line, the encroachment has been waived by the adjacent owner.	4/8/2011 5:57:31 PM

Total: 1 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)