



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198980

Date 02/16/2011	Well Owner KERR McGEE	Well No. 31-17	Lease ELLIOT
County WELD	State COLORADO	Field	
Charge to KERR McGEE OIL & GAS ONSHORE, LP			Charge Code
Address 1999 BROADWAY, SUITE 3700 (XTREME #11)			For Office Use Only
City, State DENVER, COLORADO 80202			
Pump Truck No. 1201	Code	Bulk Truck No. 1217/1218	Code
Type of Job	Depth	Fl. 660	To
Surface 8" CSG-24"	Bottom of Surface	Fl. 640	To
Plug	Plug Landed @ 596	Fl. Time On 0445	
Prediction	Pipe Landed @ 640	Fl. Time Off PLUG DOWN 0745	

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Nst TYPE III 100% EXPRESS	410	SKS		
	Poz. Mix				
	Calcium Chloride	25%	User ID 2MCL3		
	Gel % Flo-Cele 1/4 # Per Sack			WBSMONG 203 99.55 DRT	
	Handling Charge			GAL. ADST. 800 12090	
	Handling Charge				
	Additional Cement	40	SKS	14.60	
	MIXING RATE-4BPM		PRE-FLUSH	0715-0717	
	DISP. RATE-5BPM		MIXING	0717-0734	
	SLURRY VOL-1.32 CUFT³/SK		CHANGE VALVES	0734-0737	
	SLURRY WT 14.8-15.0 PPG		DISP.	0737-0745	
	WATER/CEMENT-6.25 GAL/SK		FINAL LIFT @ 310 PST		
	WATER TEMP 38°F				
	TOTAL SLURRY VOL 105.7 BBLs CEMENT				
	LANDED PLUG @ 375 PST				

Remarks: PRE-FLUSH W/10 BBLs H₂O	Tax Reference Code	Sub Total
DISPLACE W/38 BBLs H₂O	State CO 2.9 %	Tax
CIRCULATE 5 BBLs CEMENT	Disc.	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		54			
1217/1218		Bulk Truck		54/64			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JIM, OSCAR, STEVE, ADAM**

Received By

Tom Brown

Customer or His Agent