



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 306220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 198991

Date <u>2/19/11</u>	Well Owner <u>KEPP McGEE</u>	Well No. <u>22-17</u>	Lease <u>ELLIP</u>
County <u>Weld</u>	State <u>Colorado</u>		Field
Charge to <u>KEPP McGEE Oil &amp; Gas Outhouse, LP</u>			Charge Code
Address <u>1999 Broadway, Suite 3100 (Xtreme #11)</u>			For Office Use Only
City, State <u>Denver, Colorado 80202</u>			
Pump Truck No. <u>12CB</u>	Code	Bulk Truck No. <u>1218/1214</u>	Code
Type of Job		Depth	To
<u>Surface</u> <u>8 5/8" N50-34"</u>		Bottom of Surface	To
Plug		Plug Landed @ <u>574</u>	Fl. Time On <u>1045</u>
Production		Pipe Landed @ <u>618</u>	Fl. Time Off <u>Plug Pours 1300</u>

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat <u>✓ Type III 100% Excess</u>	<u>390</u>	<u>SKS</u>		
	Poz. Mix				
	Calcium Chloride	<u>25%</u>			
	Gel % Flo-Cele <u>4</u> 4Per Sack				
	Handling Charge				
	Hauling Charge				
	Additional Cement	<u>40</u>	<u>SKS</u>	<u>14.40</u>	
	Mixing Rate-4BPM	<u>1228</u>	<u>1233</u>		
	Disp. Rate-5BPM	<u>1233</u>	<u>1250</u>		
	Slurry Vol-1.32 CU FT/BK	<u>1250</u>	<u>1253</u>		
	Slurry WT 14.1-15.0 MG	<u>1253</u>	<u>1300</u>		
	Water/Cement-6.25 Gal/BK				
	Water Temp 45° F				
	Total Slurry Vol 101 BBS Cement				
	Landed Plug @ 300 PSI/FIN. LFL @ 100 PSI				

Remarks: <u>Pre-Flush w/ 20 BBS H<sup>2</sup>O</u>	Tax Reference Code	Sub Total
<u>Displace w/ 36.5 BBS H<sup>2</sup>O</u>	State <u>CO 2.9 %</u>	Tax
<u>Chaulade 7 BBS Cement</u>	Disc.	Total
Truck No.	Code	State Mileage
<u>12CB</u>		Pump Truck
<u>1218/1214</u>		Bulk Truck
		Nebraska
		Colorado
		Wyoming
		Other
		Total Mileage

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Dalko, James Justin

Received By

Customer or His Agent