



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198773

Date <u>12/20/10</u>	Well Owner <u>KERR McGEE</u>	Well No. <u>6-13</u>	Lease <u>River Bend</u>
County <u>Weld</u>	State <u>Colorado</u>		Field
Charge to <u>KERR McGEE Oil & Gas Onshore, LP</u>			Charge Code
Address <u>1999 Broadway, Suite 3700 (Xtreme #7)</u>			For Office Use Only
City, State <u>Denver, Colorado 80202</u>			
Pump Truck No. <u>1208</u>	Code	Bulk Truck No. <u>1214/1218</u>	Code
Type of Job	Depth	Fr. <u>932</u>	To
Surface <u>8 5/8" CSG-24"</u>	Bottom of Surface	Fr. <u>922</u>	To
Plug	Plug Landed @ <u>878</u>	Fr. Time On <u>0600</u>	
Production	Pipe Landed @ <u>922</u>	Fr. Time Off <u>Plug Down 1230</u>	

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Note <u>✓ Type III</u>	<u>580</u>	<u>SKS</u>		
	Poz. Mix				
	Calcium Chloride	<u>2.5%</u>	<u>MIKE LINGREEN</u>		
	Gel % Flo-Cele <u>1/4</u> #Per Sack				
	Handling Charge		<u>USER ID ZMDL8</u>		
	Handling Charge		<u>WBS/WO/CC</u>	<u>2028570</u>	<u>1 DRL</u>
	Additional Cement			<u>800/120</u>	<u>90</u>
	Mixing Rate - <u>4 BPM</u>	<u>1145-</u>	<u>1151</u>	<u>G/LACOL</u>	
	Disp Rate - <u>5 BPM</u>	<u>1151-</u>	<u>1216</u>		
	Slurry Vol - <u>1.32 cu ft/sk</u>	<u>1216-</u>	<u>1219</u>		
	Slurry Wt <u>14.8-15.0 PPG</u>	<u>1219-</u>	<u>1230</u>		
	Water/Cement - <u>6.25 Gal/sk</u>				
	Water Temp <u>64°F</u>				
	Total Slurry Vol <u>136 BBLs Cement</u>				
	Landed Plug @ <u>400 PSI</u>				

Remarks <u>Pre-Flush w/ 30 BBLs H²O</u>	Tax Reference Code	Sub Total
<u>Displace w/ 55.5 BBLs H²O</u>	State <u>CO 2.9 %</u>	Tax
<u>Circulate 6 BBLs Cement</u>	Disc.	Total

Track No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>72</u>			
<u>1214/1218</u>		Bulk Truck		<u>72/72</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Dallas, James & Sam

Received By

Ricky Tuck

Customer or His Agent