

FORM
5A

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400156216

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120 4. Contact Name: Cindy Vue
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6832
3. Address: P O BOX 173779 Fax: (720) 929-7832
City: DENVER State: CO Zip: 80217-37

5. API Number 05-123-31542-00 6. County: WELD
7. Well Name: COTTONWOOD Well Number: 32-33
8. Location: QtrQtr: NWSW Section: 33 Township: 2N Range: 66W Meridian: 6
9. Field Name: _____ Field Code: _____

Completed Interval

FORMATION: <u>NIOBRARA-CODELL</u>	Status: <u>PRODUCING</u>
Treatment Date: <u>02/15/2011</u>	Date of First Production this formation: <u>03/31/2011</u>
Perforations Top: <u>7392</u> Bottom: <u>7638</u>	No. Holes: <u>122</u> Hole size: <u>0.42</u>
Provide a brief summary of the formation treatment:	Open Hole: <input type="checkbox"/>
NB Perf 7392-7476 Holes 68 Size 0.42 CD Perf 7620-7638 Holes 54 Size 0.40 Frac Niobrara B & C down 4-1/2" Csg w/ 273 gal 15% HCl & 249,892 gal Slickwater w/ 200,520# 40/70, 4,000# SB Excel Frac Codell down 4-1/2" Csg w/ 240,505 gal Slickwater w/ 150,340# 40/70, 4,000# SB Excel	
This formation is commingled with another formation: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
Test Information:	
Date: <u>04/01/2011</u> Hours: <u>24</u> Bbls oil: <u>30</u> Mcf Gas: <u>30</u> Bbls H2O: <u>0</u>	
Calculated 24 hour rate: Bbls oil: <u>30</u> Mcf Gas: <u>30</u> Bbls H2O: <u>0</u> GOR: <u>1000</u>	
Test Method: <u>FLOWING</u> Casing PSI: <u>1680</u> Tubing PSI: <u>2300</u> Choke Size: <u>12/64</u>	
Gas Disposition: <u>SOLD</u> Gas Type: <u>WET</u> BTU Gas: <u>1193</u> API Gravity Oil: <u>47</u>	
Tubing Size: <u>2 + 3/8</u> Tubing Setting Depth: <u>7610</u> Tbg setting date: <u>03/24/2011</u> Packer Depth: _____	
Reason for Non-Production: _____	
Date formation Abandoned: _____ Squeeze: <input type="checkbox"/> Yes <input type="checkbox"/> No If yes, number of sacks cmt _____	
Bridge Plug Depth: _____ Sacks cement on top: _____	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Cindy Vue

Title: Regulatory Analyst II Date: _____ Email Cindy.Vue@anadarko.com

Based on the information provided herein, this Completed Interval Report (Form 5A) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)