


FORM 2 Rev 12/05	State of Colorado Oil and Gas Conservation Commission 1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%;">DE</td> <td style="width: 25%;">ET</td> <td style="width: 25%;">OE</td> <td style="width: 25%;">ES</td> </tr> </table> Document Number: 400138468 Plugging Bond Surety	DE	ET	OE	ES
DE	ET	OE	ES				
APPLICATION FOR PERMIT TO:							
1. <input checked="" type="checkbox"/> Drill, <input type="checkbox"/> Deepen, <input type="checkbox"/> Re-enter, <input type="checkbox"/> Recomplete and Operate							
2. TYPE OF WELL OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> COALBED <input type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/> COMMINGLE ZONE <input checked="" type="checkbox"/>		Refiling <input type="checkbox"/> Sidetrack <input type="checkbox"/>					
3. Name of Operator: <u>WILLIAMS PRODUCTION RMT COMPANY LLC</u> 4. COGCC Operator Number: <u>96850</u>							
5. Address: <u>1001 17TH STREET - SUITE #1200</u> City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80202</u>							
6. Contact Name: <u>Greg Davis</u> Phone: <u>(303)606-4071</u> Fax: <u>(303)629-8268</u> Email: <u>Greg.J.Davis@Williams.com</u>							
7. Well Name: <u>Federal</u> Well Number: <u>KP 444-18</u>							
8. Unit Name (if appl): _____ Unit Number: _____							
9. Proposed Total Measured Depth: <u>7332</u>							
WELL LOCATION INFORMATION							
10. QtrQtr: <u>SWSE</u> Sec: <u>18</u> Twp: <u>6S</u> Rng: <u>91W</u> Meridian: <u>6</u> Latitude: <u>39.522197</u> Longitude: <u>-107.594654</u>							
Footage at Surface: <u>709</u> feet FNL/FSL <u>FSL</u> 1942 feet FEL/FWL <u>FEL</u>							
11. Field Name: <u>Kokopelli</u> Field Number: <u>47525</u>							
12. Ground Elevation: <u>5918</u> 13. County: <u>GARFIELD</u>							
14. GPS Data: Date of Measurement: <u>12/16/2009</u> PDOP Reading: <u>2.3</u> Instrument Operator's Name: <u>J. Kirkpatrick</u>							
15. If well is <input checked="" type="checkbox"/> Directional <input type="checkbox"/> Horizontal (highly deviated) submit deviated drilling plan. Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL <u>518</u> <u>FSL</u> <u>647</u> <u>FEL</u> <u>518</u> <u>FSL</u> <u>647</u> <u>FEL</u> Sec: <u>18</u> Twp: <u>6S</u> Rng: <u>91W</u> Sec: <u>18</u> Twp: <u>6S</u> Rng: <u>91W</u>							
16. Is location in a high density area? (Rule 603b)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No							
17. Distance to the nearest building, public road, above ground utility or railroad: <u>902 ft</u>							
18. Distance to nearest property line: <u>1875 ft</u> 19. Distance to nearest well permitted/completed in the same formation: <u>375 ft</u>							
20. LEASE, SPACING AND POOLING INFORMATION							
Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well				
Williams Fork lles	WFILS	513-4					
Unit Configuration (N/2, SE/4, etc.)							

IMPORTANT: SOME DATA FIELDS HAVE BEEN MODIFIED.

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC51146
22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian
23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:
23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No
23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond
24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See Attached.
25. Distance to Nearest Mineral Lease Line: 518 ft 26. Total Acres in Lease: 1200

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.
28. Will salt sections be encountered during drilling? ☐ Yes ☒ No
29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No
30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No
31. Mud disposal: ☐ Offsite ☒ Onsite
Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Re-use and evaporation
Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	18	48#	0	45	25	45	0
SURF	13+1/2	9+5/8	32.3#	0	1,080	286	1,080	0
1ST	7+7/8	4+1/2	11.6#	0	7,332	661	7,332	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None
33. Comments Cement 500' above top gas. Closed Loop. See Williams Master APD dated 11/01/09. Existing Form 2A Document Number 400037551.

34. Location ID: 335529
35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No
36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Greg Davis
Title: Supervisor Permits Date: 3/29/2011 Email: Greg.J.Davis@Williams.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 4/21/2011

API NUMBER

05 045 20634 00

Permit Number: _____ Expiration Date: 4/20/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

(2) GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

(3) NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

(4) COMPLIANCE WITH THE NOTICE TO OPERATORS DRILLING WELLS IN THE BUZZARD, MAMM CREEK, AND RULISON FIELDS, GARFIELD COUNTY AND MESA COUNTY IS REQUIRED. SEE ATTACHED NOTICE.

(5) NO PORTION OF ANY PIT THAT WILL BE USED TO HOLD LIQUIDS SHALL BE CONSTRUCTED ON FILL MATERIAL, UNLESS THE PIT AND FILL SLOPE ARE DESIGNED AND CERTIFIED BY A PROFESSIONAL ENGINEER, SUBJECT TO REVIEW AND APPROVAL BY THE DIRECTOR PRIOR TO CONSTRUCTION OF THE PIT. THE CONSTRUCTION AND LINING OF THE PIT SHALL BE SUPERVISED BY A PROFESSIONAL ENGINEER OR THEIR AGENT. THE ENTIRE BASE OF THE PIT MUST BE IN CUT.

(6) THE SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 256 FEET DEEP.

Attachment Check List

Att Doc Num	Name
400138468	FORM 2 SUBMITTED
400138541	WELL LOCATION PLAT
400138542	LEGAL/LEASE DESCRIPTION
400138543	TOPO MAP
400144600	DEVIATED DRILLING PLAN
400147452	FED. DRILLING PERMIT

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Changed part of a submitted OGLA to yes	4/6/2011 4:53:14 PM

Total: 1 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)