



# FIELD TICKET & TREATMENT REPORT

## CEMENT

WIP

TICKET NUMBER

27977

**LOCATION**

Oakley KS

**FOREMAN**

Pat Heister

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
1-28-11	9160	Kerry #2	20	10 <sup>s</sup>	55 <sup>W</sup>	Lincoln
CUSTOMER Weipking-Fullerton			Limon			
MAILING ADDRESS			85			
CITY	STATE	ZIP CODE	TRUCK #	DRIVER	TRUCK #	DRIVER
			463	Miles Shuman		
			439	Pet Heister		

JOB TYPE	Surface-O	HOLE SIZE	12 1/4	HOLE DEPTH	325'	CASING SIZE & WEIGHT	8 5/8 - 23#
CASING DEPTH	323'	DRILL PIPE		TUBING		OTHER	
SLURRY WEIGHT		SLURRY VOL		WATER gal/sk		CEMENT LEFT in CASING	15'-20'
DISPLACEMENT	19 1/2	DISPLACEMENT PSI		MIX PSI		RATE	5 Bpm

REMARKS: Safety meeting, Rig up to core,  
mixed 250 sks core, 3% cc, 2% cal 1/4 # Flo-Seal  
Displace 19 1/2 BBI H<sub>2</sub>O @ 200#, shut in.

Cement + D.O Give

Thank You  
Pat & Crew

[illegible]

Ravin 3737

## AUTHORIZATION

TITLE (C-1112-11)

DATE 1/28/11

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



# CONSOLIDATED

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

TICKET NUMBER 30800  
LOCATION Oakley KS  
FOREMAN Pat Heister

## FIELD TICKET & TREATMENT REPORT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY																				
2-17-11	9160	Kerry #2	20	105	554	Lincoln																				
CUSTOMER Wierking-Fillerton			<table><tr><td>TRUCK #</td><td>DRIVER</td><td>TRUCK #</td><td>DRIVER</td></tr><tr><td>456-T118</td><td>Chad Smith</td><td></td><td></td></tr><tr><td>460</td><td>Kelly Gable</td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td></tr></table>				TRUCK #	DRIVER	TRUCK #	DRIVER	456-T118	Chad Smith			460	Kelly Gable										
TRUCK #	DRIVER	TRUCK #					DRIVER																			
456-T118	Chad Smith																									
460	Kelly Gable																									
MAILING ADDRESS																										
CITY		STATE	ZIP CODE																							

JOB TYPE <u>Prod - O</u>	HOLE SIZE <u>7 7/8</u>	HOLE DEPTH <u>7900'</u>	CASING SIZE & WEIGHT <u>5 1/2 - 17#</u>
CASING DEPTH <u>7355'</u>	DRILL PIPE	TUBING	OTHER
SLURRY WEIGHT <u>14#</u>	SLURRY VOL	WATER gal/sk <u>6.1</u>	CEMENT LEFT in CASING <u>38.10</u>
DISPLACEMENT <u>171</u>	DISPLACEMENT PSI <u>925#</u>	MIX PSI	RATE <u>7 BPPM</u>

REMARKS: Safety meeting, Run Float Equipment, Turbochargers 2  
#1-#4-#6-#8-#10-#12, Basket on #2, Port Collar on #68 w/ Basket, Cat #87-  
#69, Circ. hrs, Put 10 sks in RH, 10 sks in LH, Pump 10 BBL H<sub>2</sub>O, Sengal Water-  
Flush, 10 BBL #20. mix 135 sks H<sub>2</sub>O, 10% Salt, 5# Kol sed, 2% Cal, 1/4# Fle-Sol  
Clear Pump+lines, Displace 171 BBL H<sub>2</sub>O @ 925#, Landed Plug @  
1600#, released Pressure, Held

Thank You  
Det + Crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401P	1	PUMP CHARGE	4050. <sup>00</sup>	4050. <sup>00</sup>
5406	100	MILEAGE	5. <sup>00</sup>	500. <sup>00</sup>
115A	155 sks	class "H" Cement	22. <sup>00</sup>	3410. <sup>00</sup>
1111	7.50 #	Salt	1.42	315. <sup>00</sup>
1110A	775 #	Kelsoal	.53	410.25
1118B	290 #	Bentonite	1.24	69. <sup>00</sup>
1144G	500 gal	mud Flush	1. <sup>00</sup>	500. <sup>00</sup>
5407A	7.29	Ten Mileage Delivery	158	1,152. <sup>00</sup>
4159	1	AFU Float Shoe	413. <sup>00</sup>	413. <sup>00</sup>
4454	1	Latch down Assembly	303. <sup>00</sup>	303. <sup>00</sup>
4136	6	Turbo-Centrifuges	82. <sup>00</sup>	492. <sup>00</sup>
4130	2	Centrifuges	58. <sup>00</sup>	116. <sup>00</sup>
4104	2	Baskets	276. <sup>00</sup>	552. <sup>00</sup>
4285	1	Port Cullen	2,025. <sup>00</sup>	2,025. <sup>00</sup>
		2391001		14,358.22
		Discount 20%	-	2,871.67
				11,486.55
			SALES TAX	675. <sup>00</sup>
			ESTIMATED	
			TOTAL	12,161. <sup>55</sup>

Ravin 3737

Ravin 3737

### AUTHORIZATION

TITLE *Col Man*

DATE 2/17/11

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



## FIELD TICKET & TREATMENT REPORT

### CEMENT

TICKET NUMBER 30804  
LOCATION Oakley Ks  
FOREMAN Pat Hessler

Colonel

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
2-23-11	9160	Kerry #2	20	18 <sup>3</sup>	55 <sup>W</sup>	Lincoln
CUSTOMER Wiepking - Fullerton						
MAILING ADDRESS						
CITY		STATE	ZIP CODE			

TRUCK #	DRIVER	TRUCK #	DRIVER
463	Miles Shew		
439	Kim		

JOB TYPE <i>Part Celler</i>	HOLE SIZE	HOLE DEPTH	CASING SIZE & WEIGHT <i>5 1/2 - 17#</i>
CASING DEPTH	DRILL PIPE	TUBING <i>2 7/8 -</i>	OTHER
SLURRY WEIGHT	SLURRY VOL	WATER gal/sk	CEMENT LEFT in CASING <i>-</i>
DISPLACEMENT	DISPLACEMENT PSI	MIX PSI	RATE

REMARKS: Safety Meeting, rig up to well, Test casing to 1500 # Held  
upon Port Collar, Pump into, Have cure. Mixed 200 SKS 60% por.  
6% Gel, 5# Kcl/seal, 2% cc, 1/4# Flo-Seal. Displaced 26 BBL it 20  
@ 1300# max, shut Tool, Test to 1500#, Held. ran 6 JTs and reversed  
out clean.

Thank You  
Pat + Crew

[illegible]

Ravin 3737

### AUTHORIZATION

**TITLE**

DATE \_\_\_\_\_

**I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.**