


FORM 5 Rev 02/08	State of Colorado Oil and Gas Conservation Commission 1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%;">DE</td> <td style="width: 25%;">ET</td> <td style="width: 25%;">OE</td> <td style="width: 25%;">ES</td> </tr> </table> Document Number: 400099617	DE	ET	OE	ES
DE	ET	OE	ES				
DRILLING COMPLETION REPORT							
This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.							
Completion Type <input checked="" type="checkbox"/> Final completion <input type="checkbox"/> Preliminary completion							
1. OGCC Operator Number: 100322 2. Name of Operator: NOBLE ENERGY INC 3. Address: 1625 BROADWAY STE 2200 City: DENVER State: CO Zip: 80202		4. Contact Name: EILEEN ROBERTS Phone: (303) 2284330 Fax: (303) 2284286					
5. API Number 05-123-30683-00 7. Well Name: WELLS RANCH 8. Location: QtrQtr: SWNE Section: 26 Township: 6N Range: 63W Meridian: 6 Footage at surface: Distance: 1810 feet Direction: FNL Distance: 1947 feet Direction: FEL As Drilled Latitude: 40.459790 As Drilled Longitude: -104.401630		6. County: WELD Well Number: 26-07X					
GPS Data: Data of Measurement: 07/22/2010 PDOP Reading: 3.9 GPS Instrument Operator's Name: Paul Tappy							
** If directional footage at Top of Prod. Zone Dist.: feet. Direction: Dist.: feet. Direction: Sec: Twp: Rng: ** If directional footage at Bottom Hole Dist.: feet. Direction: Dist.: feet. Direction: Sec: Twp: Rng:							
9. Field Name: WATTENBERG 11. Federal, Indian or State Lease Number:		10. Field Number: 90750					
12. Spud Date: (when the 1st bit hit the dirt) 07/16/2010 13. Date TD: 07/19/2010 14. Date Casing Set or D&A: 07/22/2010							
15. Well Classification: <input type="checkbox"/> Dry <input checked="" type="checkbox"/> Oil <input type="checkbox"/> Gas/Coalbed <input type="checkbox"/> Disposal <input type="checkbox"/> Stratigraphic <input type="checkbox"/> Enhanced Recovery <input type="checkbox"/> Storage <input type="checkbox"/> Observation							
16. Total Depth MD 7020 TVD**		17 Plug Back Total Depth MD 6950 TVD**					
18. Elevations GR 4857 KB 4873		One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.					
19. List Electric Logs Run: CDL/CNL/ML, DIL/GLL/GRL, GRL/CCL/CBL/VDL							
20. Casing, Liner and Cement:							

IMPORTANT: SOME DATA FIELDS HAVE BEEN MODIFIED.

CASING									
Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	32.00	0	561	243	0	575	CALC
1ST	7+7/8	4+1/2	11.60	0	6,995	575	1,747	6,995	CBL

ADDITIONAL CEMENT

Cement work date: _____

Details of work:

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
NIOBRARA	6,538		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	6,812		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	6,836		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Eileen Roberts

Title: Regulatory Specialist Date: 11/4/2010 Email: eroberts@nobleenergyinc.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400099627	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Directional Survey **	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400099617	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Permit	REQ HARD COPY DEN/NEU/ML	12/29/2010 11:59:01 AM
Permit	Rec hard copy DIL LOG 1290836, sent to scanning	11/8/2010 1:38:14 PM

Total: 2 comment(s)

Date Run: 4/25/2011 Doc [#400099617] Well Name: WELLS RANCH 26-07X

Page 2 of 3

IMPORTANT: SOME DATA FIELDS HAVE BEEN MODIFIED.