

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☐  
Sidetrack ☐

Document Number:

400154768

Plugging Bond Surety

20060137

3. Name of Operator: OXY USA WTP LP

4. COGCC Operator Number: 66571

5. Address: P O BOX 27757

City: HOUSTON State: TX Zip: 77227

6. Contact Name: Joan Proulx Phone: (970)263.3641 Fax: (970)263.3694  
Email: joan\_proulx@oxy.com

7. Well Name: Cascade Creek Well Number: 697-04-65B

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 9446

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 4 Twp: 6S Rng: 97W Meridian: 6

Latitude: 39.548760 Longitude: -108.230230

Footage at Surface: 1480 feet FNL/FSL FSL 1108 feet FEL/FWL FWL

11. Field Name: Grand Valley Field Number: 31290

12. Ground Elevation: 8648 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 04/08/2011 PDOP Reading: 1.5 Instrument Operator's Name: R. Seal

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1413 FSL 614 FWL FWL Bottom Hole: FNL/FSL 1413 FSL 614 FWL FWL  
Sec: 4 Twp: 6S Rng: 97W Sec: 4 Twp: 6S Rng: 97W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 6693 ft

18. Distance to nearest property line: 4273 ft 19. Distance to nearest well permitted/completed in the same formation: 330 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	510-48		
Williams Fork	WMFK	510-15		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
See attached Mineral Lease Description

25. Distance to Nearest Mineral Lease Line: 3818 ft 26. Total Acres in Lease: 9640

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24+0/0	16+0/0	65	0	90	4	90	0
SURF	14+3/4	9+5/8	36	0	2,690	1,210	2,690	0
1ST	8+3/4	4+1/2	11.6	0	9,331	1,849	9,331	5,801

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Oxy is both the surface and mineral owner; Rules 305 and 306 are waived. The well pad has not been constructed. A semi-closed loop system will be used. Per GarCo Vacation Ordinance dated 10-5-1987, CR 213 is now OXY's private property north of Sec 8, 7S, 97W, 6 PM. Oxy will provide appropriate housing for essential personnel in order to conduct safe, efficient drilling operations at this well site. Oxy will comply with Notice to Operators (NTO) Drilling wells on the Roan Plateau (June 12, 2008). The CDOW pre-consultation meeting occurred on Feb. 11, 2011.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Joan Proulx

Title: Regulatory Analyst Date: \_\_\_\_\_ Email: joan\_proulx@oxy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

API NUMBER

05

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

**Attachment Check List**

Att Doc Num	Name
400154778	MINERAL LEASE MAP
400154781	TOPO MAP
400154783	DEVIATED DRILLING PLAN
400154784	WELL LOCATION PLAT

Total Attach: 4 Files

**General Comments**

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

**BMP**

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)