

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400155975

Plugging Bond Surety

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☐

Sidetrack ☐

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY LLC

4. COGCC Operator Number: 96850

5. Address: 1001 17TH STREET - SUITE #1200

City: DENVER State: CO Zip: 80202

6. Contact Name: Howard Harris Phone: (303)606-4086 Fax: (303)629-8268  
Email: howard.harris@williams.com

7. Well Name: Federal Well Number: RGU 24-25-198

8. Unit Name (if appl): Ryan Gulch Unit Unit Number: COC068239  
X

9. Proposed Total Measured Depth: 12727

WELL LOCATION INFORMATION

10. QtrQtr: Lot 14 Sec: 25 Twp: 1S Rng: 98W Meridian: 6

Latitude: 39.928055 Longitude: -108.346257

Footage at Surface: 332 feet FNL/FSL 1418 feet FEL/FWL  
FSL FWL

11. Field Name: Sulphur Creek Field Number: 80090

12. Ground Elevation: 6684 13. County: RIO BLANCO

14. GPS Data:

Date of Measurement: 02/24/2011 PDOP Reading: 1.0 Instrument Operator's Name: J. Kirkpatrick

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1034 FSL 1912 FWL 1034 FSL 1912 FWL  
Bottom Hole: FNL/FSL 1034 FSL 1912 FWL  
Sec: 25 Twp: 1S Rng: 98W Sec: 25 Twp: 1S Rng: 98W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 613 ft

18. Distance to nearest property line: 7157 ft 19. Distance to nearest well permitted/completed in the same formation: 639 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	Unspaced		Unspaced
Sego	SEGO			
Wasatch	WSTC			
Williams Fork	WMFk			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC 60733

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
See Attached

25. Distance to Nearest Mineral Lease Line: 1034 ft 26. Total Acres in Lease: 1238

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Re-Use, Evap & Backfill

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	30	18	48	0	80	100	80	0
SURF	14+3/4	9+5/8	36	0	3,918	1,570	3,918	0
1ST	8+3/4	4+1/2	11.6	0	12,727	1,056	12,727	7,627

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Top of cement for production casing will be approx 200 feet above top of Mesaverde. Federal minerals and Surface. See Williams Production RMT Master 10 Point Drilling Plan dated 3/24/11 for all specific drilling stipulations. Closed mud system.

34. Location ID: 316657

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Howard Harris

Title: Sr. Regulatory Specialist Date: \_\_\_\_\_ Email: Howard.Harris@Williams.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

**API NUMBER**

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

--

**Attachment Check List**

Att Doc Num	Name
400160009	WELL LOCATION PLAT
400160010	LEGAL/LEASE DESCRIPTION
400160011	FED. DRILLING PERMIT
400160012	DEVIATED DRILLING PLAN
400160013	DEVIATED DRILLING PLAN

Total Attach: 5 Files

**General Comments**

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

**BMP**

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)