

FORM  
17Rev  
6/99State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400155433

## BRADENHEAD TEST REPORT

Step 1. Record all tubing and casing pressures as found. Step 2. Sample now. If intermediate or surface casing pressure > 25 psi. In sensitive areas, 1 psi.  
Step 3. Conduct Bradenhead test. Step 4. Conduct intermediate casing test. Step 5. Send report to BLM within 3 days and to OGCC within 10 days. Include wellbore diagram if not previously submitted or if wellbore configuration has changed since prior program. Attach gas and liquid analyses if sampled.

1. OGCC Operator Number: 47120 3. BLM Lease No: \_\_\_\_\_  
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP  
4. API Number: 05-123-09013- 5. Multiple completion? ☐ Yes ☐ No  
6. Well Name: UPRR 38 PAN AM E 1 Number: \_\_\_\_\_  
7. Location (QtrQtr, Sec, Twp, Rng, Meridian): SWNE,3,2N,66W,6  
8. County WELD 9. Field Name: WATTENBERG  
10. Minerals: ☐ Fee ☐ State ☐ Federal ☐ Indian

11. Date of Test: 01/18/2011

12. Well Status: ☐ Flowing  
☐ Shut In ☐ Gas Lift  
☐ Pumping ☐ Injection  
☐ Clock/Intermitter  
☒ Plunger Lift

13. Number of Casing Strings:  
☐ Two ☐ Three ☐ Liner?

## 14. EXISTING PRESSURES

Record all pressures as found	Tubing: _____ Fm: _____	Tubing: 151 Fm: _____	Prod Csg 193 Fm: _____	Intermediate Csg: _____	Surf. Csg 0
-------------------------------	----------------------------	--------------------------	---------------------------	----------------------------	----------------

## BRADENHEAD TEST

Buried valve? ☒ Yes ☐ NoConfirmed open? ☒ Yes ☐ No

With gauges monitoring production, intermediate casing and tubing pressures, open surface casing (bradenhead) valve (if no intermediate casing, monitor only the production casing and tubing pressures.)  
Record pressures at five minute intervals Define characteristics of flow in "Bradenhead Flow" column using letter designations below:  
O = No Flow; C = Continuous; D = Down to 0; V = Vapor  
H = Water H2O; M = Mud; W = Whisper; S = Surge; G = Gas

BRADENHEAD SAMPLE TAKEN?

☐ Yes ☒ No ☐ Gas ☐ LiquidCharacter of Bradenhead fluid: ☐ Clear ☐ Fresh☐ Sulfur ☐ Salty ☐ Black

Other:(describe)

Sample cylinder number: \_\_\_\_\_

Elapsed Time (Min:Sec)	Fm: Tubing	Fm: Tubing:	Prod Csg PSIG	Intermedia Csg PSIG	Bradenhead Flow:
00:00		151	193		W
05:00		155	197		D
10:00		159	200		O
15:00		164	204		O
20:00		169	206		O
25:00		172	207		O
30:00		177	209		O

Instantaneous Bradenhead PSIG at end of test: &gt; 0

## INTERMEDIATE CASING TEST

Buried valve? ☐ Yes ☐ NoConfirmed open? ☐ Yes ☐ No

With gauges monitoring production, intermediate casing and tubing pressures, open the intermediate casing valve. Record pressures at five minute intervals Characterize flow in "Intermediate Flow" column using letter designations below:  
O = No Flow; C = Continuous; D = Down to 0; V = Vapor  
H = Water H2O; M = Mud; W = Whisper; S = Surge; G = Gas

INTERMEDIATE SAMPLE TAKEN?

☐ Yes ☐ No ☐ Gas ☐ LiquidCharacter of Intermediate fluid: ☐ Clear ☐ Fresh☐ Sulfur ☐ Salty ☐ Black

Other:(describe)

Sample cylinder number: \_\_\_\_\_

Elapsed Time (Min:Sec)	Fm: Tubing	Fm: Tubing:	Prod Csg PSIG	Intermedia Csg PSIG	Bradenhead Flow:

Instantaneous Intermediate Casing PSIG at end of test: &gt;

Comments: Blew down immediately did not pressure up in 10 minutes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Test Performed By: Tyler Mantz Title: \_\_\_\_\_ Phone: (970) 380-4454

Signed: Mike Weaver Title: Product Engineer Date: 4/14/2011  
Manager

Witnessed By: \_\_\_\_\_ Title: \_\_\_\_\_ Agency: \_\_\_\_\_