

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

2. TYPE OF WELL

OIL  GAS  COALBED  OTHER \_\_\_\_\_  
SINGLE ZONE  MULTIPLE ZONE  COMMINGLE ZONE

Refiling   
Sidetrack

Document Number:  
400156879  
Plugging Bond Surety  
20040071

3. Name of Operator: ANTERO RESOURCES PICEANCE CORPORATION 4. COGCC Operator Number: 10079

5. Address: 1625 17TH ST STE 300  
City: DENVER State: CO Zip: 80202

6. Contact Name: Hannah Knopping Phone: (303)357-6412 Fax: (303)357-7315  
Email: hknopping@anteroresources.com

7. Well Name: McPherson Well Number: A8

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 7682

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 16 Twp: 6S Rng: 92W Meridian: 6  
Latitude: 39.531112 Longitude: -107.675773

Footage at Surface: 1043 feet <sup>FNL/FSL</sup> FNL 1542 feet <sup>FEL/FWL</sup> FWL

11. Field Name: Mamm Creek Field Number: 52500

12. Ground Elevation: 5448 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 01/04/2011 PDOP Reading: 2.5 Instrument Operator's Name: Scott E. Aibner

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: <sup>FNL/FSL</sup> 297 FNL 1223 <sup>FEL/FWL</sup> FWL Bottom Hole: <sup>FNL/FSL</sup> 297 FNL 1223 <sup>FEL/FWL</sup> FWL  
Sec: 16 Twp: 6S Rng: 92W Sec: 16 Twp: 6S Rng: 92W

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 700 ft

18. Distance to nearest property line: 225 ft 19. Distance to nearest well permitted/completed in the same formation: 680 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	191-34	160	NW/4
Williams Fork	WMFK	191-34	160	NW/4

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: \_\_\_\_\_

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bon  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
Section 16, T6S, R92W: Portion of the N/2NWNW (See lease map previously submitted)

25. Distance to Nearest Mineral Lease Line: 94 ft 26. Total Acres in Lease: 16

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?  Yes  No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)?  Yes  No

31. Mud disposal:  Offsite  Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method:  Land Farming  Land Spreading  Disposal Facility Other: Onsite.if app.(see comments)

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	55#	0	60	177	60	0
SURF	12+1/4	8+5/8	24/32#	0	1,000	416	1,000	0
1ST	7+7/8	4+1/2	11.6#	0	7,682	356	7,682	

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None

33. Comments I certify that conditions from the last approved permit are the same except updated SHL and BHL, updated lease information, and casing/cementing program has been updated. There have been no other changes to land use, well construction or the lease. This Refile Form 2 does not require a Form 2A because the pad has been constructed, a closed loop system is being used so no pits need to be constructed, the refiled well will not require any expansion / additional surface disturbance of the pad. The location is not in a wildlife restricted surface occupancy area (RSO); consultation with CDOW is not required and the location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii).; consultation with CDPHE is not required. Please note, however, that a Form 2A has been filed per Rule 303d.(1) in conjunction with a new well that is being added to this pad (the McPherson A10). #19: Please note that the Hangs B8 BHL has moved farther away from the McPherson A8 than what currently shows on COGCC map and will be re-permitted with correct BHL shortly. #31 Mud Disposal: Antero will bury onsite if disposal meets Table 910 and if there is a provision in SUA which allows for such operation. TOP OF CEMENT OF 1ST STRING/PRODUCTION CASING WILL BE >500 FEET ABOVE TOP OF GAS.

34. Location ID: 335539

35. Is this application in a Comprehensive Drilling Plan ?  Yes  No

36. Is this application part of submitted Oil and Gas Location Assessment ?  Yes  No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Hannah Knopping

Title: Permit Representative Date: 4/28/2011 Email: hknopping@anteroresources.co

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

<b>API NUMBER</b>
05 045 14475 00

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

**CONDITIONS OF APPROVAL, IF ANY:** \_\_\_\_\_

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

**Attachment Check List**

Att Doc Num	Name
400159785	WELL LOCATION PLAT
400159787	30 DAY NOTICE LETTER
400159790	DEVIATED DRILLING PLAN

Total Attach: 3 Files

**General Comments**

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

**BMP**

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)